

3 023419

15-001-02500-00-00

To:

API NUMBER 20080046-040

STATE CORPORATION COMMISSION

NE,SE,SE 1/4 Sec/Twp/Rge S.14-T.26S.-R.18E.

Wichita State Office Bldg. - PLUGGING SECTION

1214 feet from south section line

130 S. Market, Room 2078

492 feet from east section line

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Lease/Well# LOCKHART NO. 40

Operator License #

100101

County

ALLEN

Operator: STATE OF KANSAS

Well Total Depth 850 feet

Name & FEE FUND PLUGGING

Production Pipe: 2" Size Feet 850

Address

Surface Casing: 12" Size Feet 20'

AB oil well ☒ Gas Well ☐ SWD Well/ Input Well ☐D & A ☐

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE, LLC

Lic. #

33749
30670

Address: 19245 FORD RD., CHANUTE, KS. 66720

Company to plug at: Hour: 1:30 P.M. Day: 17 Month: 7 2008

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL ORIGINALLY CONSISTED OF 2" CASING TO 850' THAT HAD

BEEN CEMENTED IN AT T.D. ONLY. AT SOME TIME IN THE PAST, THE 2" PARTED

AND WAS REMOVED. THE PLUGGING PROPOSAL WAS TO CIRCULATE AS MUCH

OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent: All ☐ Part ☐

TECHNICIAN

None ☐ X ☒

Operations Completed: Hour: 3:30 P.M. Day: 17 Month: 7 2008

Actual Plugging Report: 1" PIPE WAS RAN INTO THE SURFACE CASING TO 285'. CEMENT

WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING

AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

137 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION POINT NO. 40) (THIS WELL WAS NOT NUMBERED ON THE LEASE MAP.)

(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 25 2008

CONSERVATION DIVISION
WICHITA, KS

Signed:

Clayton P. Titel
TECHNICIAN

PCT