

3 023404

15-001-02502-00-00

To:

API NUMBER 20080046-006

STATE CORPORATION COMMISSION

SE,SW,SE 1/4 Sec/Twp/Rge S.14-T.26S.-R.18E.

Wichita State Office Bldg. - PLUGGING SECTION

571 feet from south section line

130 S. Market, Room 2078

1387 feet from east section line

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Lease/Well# LOCKHART NO. A-13

Operator License # 100101

County ALLEN

Operator: STATE OF KANSAS

Well Total Depth 850 feet

Name & FEE FUND PLUGGING

Production Pipe: 2" Size Feet 850

Address

Surface Casing: 8" Size Feet 20'

AB oil well Gas Well SWD Well/ Input Well E-591 D & A

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE, LLC

Lic. # 33749 30670

Address: 19245 FORD RD., CHANUTE, KS. 66720

Company to plug at: Hour: 8:00A.M. Day: 2 Month: 7 2008

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 850' THAT

MAY HAVE BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL

WAS TO PERFORATE THE CASING AND TO CIRCULATE AS MUCH OF THE WELL AS

POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All Part None X

Operations Completed: Hour: 11:00A.M. Day: 2 Month: 7 2008

Actual Plugging Report: THE 2" CASING WAS DRILLED OUT TO 500'. 1" PIPE WAS

RAN INTO THE 2" CASING TO 500'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL

CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE 1" PIPE WAS REMOVED.

DISPLACEMENT WAS FILLED FROM SURFACE. 130 SACKS OF CEMENT WERE PUMPED

INTO THIS WELL.

Remarks: (GPS SESSION POINT NO. 06) (THIS WELL WAS WELL NO.A-13 ON THE LEASE MAP.)

(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 21 2008

CONSERVATION DIVISION
WICHITA, KS

Signed:

Clayton P. Titel
TECHNICIAN

PKG