

3 023379

15-001-02503-00-00

To:
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 20080046-005
SW,SE,SE 1/4 Sec/Twp/Rge S.14-T.26S.-R.18E.
611 feet from south section line
1160 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 100101Lease/Well# LOCKHART NO. B-12AOperator: STATE OF KANSASCounty ALLENName & FEE FUND PLUGGINGWell Total Depth 850 feet

Address _____

Production Pipe: 2" Size Feet 850Surface Casing: 8" Size Feet 20'AB oil well X Gas Well _____ SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERVICE, LLC Lic. # 30670Address: 19245 FORD RD., CHANUTE, KS. 66720Company to plug at: Hour: 11:00 A.M. Day: _____ 19 Month: 5 2008Plugging proposal received from: CLAYTON P. TITELCompany Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 850' THAT MAY
HAVE BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPSAL WAS
TO PERFORATE THE 2" CASING AND TO CIRCULATE AS MUCH OF THE WELL AS
POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITELPlugging attended by Agent: All _____ Part X None _____Operations Completed: Hour: 1:00P.M. Day: _____ 19 Month: 5 2008Actual Plugging Report: THE 2" CASING WAS PERFORATED AT 200' AND AT 500'.

1" PIPE WAS RAN INTO THE 2" CASING TO 655'. CEMENT WAS PUMPED INTO THE 1"
PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE 1" PIPE
WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 112 SACKS OF CEMENT
WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION POINT NO. 05) (THIS WELL WAS WELL NO.B-12A ON THE LEASE MAP.)
(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed:

Clayton P. Titel
TECHNICIAN

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 23 2008

CONSERVATION DIVISION
WICHITA, KS