

3 023378

15-001-02504-00-00

To:

API NUMBER 20080046-0004

STATE CORPORATION COMMISSION

SE,SW,SE 1/4 Sec/Twp/Rge S.14-T.26S.-R.18E.

Wichita State Office Bldg. - PLUGGING SECTION

205 feet from south section line

130 S. Market, Room 2078

1484 feet from east section line

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Lease/Well# LOCKHART NO. B-16

Operator License # 100 101

County ALLEN

Operator: STATE OF KANSAS

Well Total Depth 850 feet

Name & FEE FUND PLUGGING

Production Pipe: 2" Size Feet 850

Address

Surface Casing: 8" Size Feet 20'

AB oil well ☒ Gas Well ☐ SWD Well/ Input Well ☐ D & A ☐

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE, LLC

Lic. # 33749 30670

Address: 19245 FORD RD., CHANUTE, KS. 66720

Company to plug at: Hour: 3:00 P.M. Day: 19 Month: 5 2008

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 850' THAT MAY

HAVE BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPSAL WAS

TO PERFORATE THE 2" CASING AND TO CIRCULATE AS MUCH OF THE WELL AS

POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All ☒ Part ☐TECHNICIAN
None

Operations Completed: Hour: 5:00P.M. Day: 19 Month: 5 2008

Actual Plugging Report: THE 2" CASING WAS PERFORATED AT 200' AND AT 500'.

1" PIPE WAS RAN INTO THE 2" CASING TO 725'. CEMENT WAS PUMPED INTO THE 1"

PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE 1" PIPE

WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 48 SACKS OF CEMENT

WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION POINT NO. 04) (THIS WELL WAS WELL NO.B-16 ON THE LEASE MAP.)

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed:

Clayton P. Titel

RECEIVED
TECHNICIAN
KANSAS CORPORATION COMMISSION

JUN 23 2008

CONSERVATION DIVISION
WICHITA, KS