

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER 15-091-19162-00-00
swne sene
SWSWNW Sec/Twp/Rge 2-13S-25E

3369 feet from south section line

607 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Lease/Well# WOOLARD #01

Operator License # 101

County JOHNSON

Operator: STATE OF KANSAS

Well Total Depth 370 feet

Name & FEE FUND

Production Pipe: 2" Size Feet NA

Address CHANUTE DISTRICT OFFICE

Surface Casing: NA Size Feet NA

AB oil well _____ Gas Well XXXX SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERVICE, LLC

Lic. # 33749

Address: 19245 FORD ROAD CHANUTE, KS 66720

Company to plug at: Hour: 9:00 AM Day: _____ 6 Month: 11 2007

Plugging proposal received from: JIM KEPLEY

Company Name: KEPLEY WELL SERVICE, LLC

Phone: 620-431-9212

Were: PUMP WELL FULL OF CEMENT.

Plugging Proposal Received by: TAYLOR HERMAN

TECHNICIAN

Plugging attended by Agent: All XXXX Part _____

None _____

Operations Completed: Hour: 4:00 PM Day: _____ 6 Month: 11 2007

Actual Plugging Report: RAN 1" SPOOLER INSIDE 2" CASING DOWN TO 370'. PULLED OUT 1" AND PERFORATED THE 2" CASING AT 170' AND 70'. RAN 1" BACK DOWN 2" CASING AND TRIED TO WASH DOWN. PUMPED CEMENT FROM 370' TO SURFACE. PULLED OUT 1" AND HOOKED ON TO 2" CASING AND SQUEEZED CEMENT. A TOTAL OF 140 SACKS OF CEMENT WERE PUMPED.

Remarks: CONTRACT # 7779 CONTROL #20080033-001 OLD STYLE WELL COMPLETION.

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed: TAYLOR HERMAN

TECHNICIAN

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 26 2007

CONSERVATION DIVISION
WICHITA, KS