

3 023162

15-207-02039-00-00

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 100 ¹⁰¹Operator: STATE OF KANSASName & FEE FUND PLUGGING

Address _____

AB oil well ☒ Gas Well _____ SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERVICE, LLC Lic. # 30670 ³³⁷⁴⁹Address: 19245 FORD RD., CHANUTE, KS. 66720Company to plug at: Hour: 8:00A.M. Day: _____ 29 Month: 5 2007Plugging proposal received from: CLAYTON P. TITELCompany Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 4 1/2" CASING TO APPROXIMATELY 1100' THAT HAD BEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO PERFORATE THE 4 1/2" CASING AND TO CIRUCLATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT INSIDE AND OUSIDE THE 4 1/2" CASING.

Plugging Proposal Received by: CLAYTON P. TITELPlugging attended by Agent: All ☒ Part _____ None _____Operations Completed: Hour: 12:00P.M. Day: _____ 29 Month: 5 2007Actual Plugging Report: THE 4 1/2" CASING WAS PERFRATED AT 700' AND AT 200'.1" PIPE WAS RAN INTO THE 4 1/2" CASING TO 1100'. CEMENT WAS PUMPED INTO THE 1"PIPE UNTIL CEMENT CIRCULATED BOTH THE 4 1/2" CASING AND FROM THE 4 1/2" AND 6"ANNULUS AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROMSURFACE. 230 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

RECEIVED

JUN 11 2007

Remarks: (SPOT LOCTION ESTABLISHED BY GPS AS NO. YOU4)
(If additional description is necessary, use BACK of this form.)

KCC WICHITA

I DID observe this plugging.

Signed:

Clayton P. Titel
TECHNICIAN
KANSAS CORPORATION COMMISSION

JUN 11 2007

CONSERVATION DIVISION
WICHITA, KS