

3 022988

15-001-27,971-00-00

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER CONTROL NO. 20060001--044
SE,NW,NE 1/4 Sec/Twp/Rge S.24-T.26S.-R.17E.
4516 feet from south section line
1880 feet from east section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 100101
Operator: STATE OF KANSAS Fee Funds

Lease/Well# JONES NO.17
County ALLEN
Well Total Depth 900' feet
Production Pipe: 2 7/8" Size Feet 827.6'
Surface Casing: 7" Size Feet 35'

Name & _____
Address _____

AB oil well _____ Gas Well _____ SWD Well/ Input Well E-25,204 D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERVICE, LLC Lic. # 30870

Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 10:00A.M. Day: _____ Month: 12 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2 7/8 " CASING TO 827.6'

THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING

PROPOSAL WAS TO SQUEEZE THE 2 7/8" CASING FULL OF CEMENT

FROM SURFACE.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All Part _____ None _____
TECHNICIAN

Operations Completed: Hour: 12:00P.M. Day: _____ Month: 12 2005

Actual Plugging Report: THE PUMP TRUCK WAS CONNECTED DIRECTLY TO

THE 2 7/8" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE

CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 2 7/8" CASING UNTIL

THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 1200P.S.I..

27 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

RECEIVED
KCC DISTRICT #5

FEB 1 2006

Remarks: (GPS SESSION PT. NO.7.) (THIS WAS API NO. 15-001-27,971-00-01.)

(If additional description is necessary, use BACK of this form.)

CHANUTE, KS

I DID observe this plugging.

Signed:

Clayton P. Titel
TECHNICIAN

RECEIVED
JAN 19 2006
KCC WICHITA

RECEIVED
FEB 03 2006
KCC WICHITA

33749

0

PT