

3 023409

15-001-02519-00-00

To:

API NUMBER 20080046-042

STATE CORPORATION COMMISSION

NW,SE,SE 1/4 Sec/Twp/Rge S.14-T.26S.-R.18E.

Wichita State Office Bldg. - PLUGGING SECTION

1038 feet from south section line

130 S. Market, Room 2078

728 feet from east section line

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Lease/Well# LOCKHART NO. FF-10A

Operator License # 106601

County ALLEN

Operator: STATE OF KANSAS

Well Total Depth 850 feet

Name & FEE FUND PLUGGING

Production Pipe: 2" Size Feet 850

Address

Surface Casing: 8" Size Feet 20'

AB oil well ☒ Gas Well ☐ SWD Well/ Input Well ☐

D & A

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE, LLC

Lic. # 30670

Address: 19245 FORD RD., CHANUTE, KS. 66720

Company to plug at: Hour: 1:00P.M. Day: 1 Month: 7 2008

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 850' THAT

MAY HAVE BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING

PROPOSAL WAS TO PERFORATE THE 2" CASING AND TO CIRCULATE AS

MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All ☒ Part

TECHNICIAN

None

Operations Completed: Hour: 4:00P.M. Day: 1 Month: 7 2008

Actual Plugging Report: THE 2' CASING WAS PERFORATED AT 200' AND AT

500'. 1" PIPE WAS RAN INTO THE 2" CASING TO 775'. CEMENT WAS PUMPED INTO THE

1" PIPE UNTIL CEMENT CIRCULATED FROM THE CASING AT SURFACE. THE 1" PIPE

WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 29 SACKS OF CEMENT

WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION POINT NO. 42) (THIS WELL WAS WELL NO.FF-10A ON THE LEASE MAP.)

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 21 2008

CONSERVATION DIVISION
WICHITA, KS

Signed:

Clayton P. Titel
TECHNICIAN

PT