

3 023421

15-001-02532-00-00

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER 20080046-043  
NE,SE,SE 1/4 Sec/Twp/Rge S.14-T.26S.-R.18E.  
1080 feet from south section line  
390 feet from east section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 100 101  
Operator: STATE OF KANSAS  
Name & FEE FUND PLUGGING  
Address \_\_\_\_\_

Lease/Well# LOCKHART NO. GG-H  
County ALLEN  
Well Total Depth 850 feet  
Production Pipe: 2" Size Feet 850  
Surface Casing: 8" Size Feet 20'

AB oil well \_\_\_\_\_ Gas Well \_\_\_\_\_ SWD Well/ Input Well \_\_\_\_\_  
Other well as hereinafter indicated: \_\_\_\_\_

Plugging Contractor: KEPLEY WELL SERVICE, LLC Lic. # 30670  
Address: 19245 FORD RD., CHANUTE, KS. 66720

Company to plug at: Hour: 8:00A.M. Day: \_\_\_\_\_ 18 Month: 7 2008

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL ORIGINALLY CONSISTED OF 2" CASING TO 850' THAT HAD  
BEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE  
AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All \_\_\_\_\_ Part \_\_\_\_\_ TECHNICIAN  
None \_\_\_\_\_ X \_\_\_\_\_

Operations Completed: Hour: 11:00A.M. Day: \_\_\_\_\_ 18 Month: 7 2008

Actual Plugging Report: ! PIPE WAS RAN INTO THE 2" CASING TO 725'. CEMENT  
WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING  
AT SURFACE. THE 1" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE 2" AND 8"  
ANNULUS TO 325'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED  
FROM THE SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT  
WAS FILLED FROM SURFACE. 119 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION POINT NO. 43) (THIS WELL WAS NO. GG-11 ON THE LEASE MAP.)  
(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

RECEIVED  
KANSAS CORPORATION COMMISSION  
Signed:

AUG 25 2008

CONSERVATION DIVISION  
WICHITA, KS

Clayton P. Titel  
TECHNICIAN

33749