

3 023414

15-001-02506-00-00

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER 20080046-059

SW,SW,SE 1/4 Sec/Twp/Rge S.14-T.26S.-R.18E.

587 feet from south section line

1734 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 100101

Operator: STATE OF KANSAS

Name & FEE FUND PLUGGING

Address

AB oil well Gas Well SWD Well/ Input Well E-591 D & A

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE, LLC Lic. # 30870

Address: 19245 FORD RD., CHANUTE, KS. 66720

Company to plug at: Hour: 8:00A.M. Day: 1 Month: 8 2008

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 850' THAT

HAD BEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO

CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All X Part None

Operations Completed: Hour: 12:00P.M. Day: 8 Month: 1 2008

Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2" CASING TO 650'.

CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM

THE 2" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. 1" PIPE WAS RAN

INTO THE 2" AND 8" ANNULUS TO 425'. CEMENT WAS PUMED INTO THE 1" PIPE

UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE

1" WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 117 SACKS

OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION POINT NO. 49) (THIS WAS WELL NO.C-13 ON THE LEASE MAP.)

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

RECEIVED
KANSAS CORPORATION COMMISSION Signed:

AUG 21 2008

CONSERVATION DIVISION
WICHITA, KSClayton P. Titel
TECHNICIAN

33749