

3 023355

15-001-02392-00-00

To:

API NUMBER 20080046-002

STATE CORPORATION COMMISSION

SW,SW,SE 1/4 Sec/Twp/Rge S.14-T.26S.-R.18E.

Wichita State Office Bldg. - PLUGGING SECTION

158 feet from south section line

130 S. Market, Room 2078

2177 feet from east section line

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Lease/Well# LOCKHART NO. F-16A

Operator License # 101 100

County ALLEN

Operator: STATE OF KANSAS

Well Total Depth 850 feet

Name & FEE FUND PLUGGING

Production Pipe: 2" Size Feet 850

Address

Surface Casing: 8" Size Feet 20'

AB oil well ☒ Gas Well ☐ SWD Well/ Input Well ☐

D & A

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE, LLC

Lic. #

30670 33749

Address: 19245 FORD RD., CHANUTE, KS. 66720

Company to plug at: Hour: 11:00A.M. Day: 14 Month: 4 2008

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: VISIBLE AT SURFACE ON THIS WELL WAS 2" IN 6" IN 8". THE PLUGGING PROPOSAL

WAS TO PERFORATE THE CASINGS AND TO CIRCULATE AS MUCH OF THE WELL AS

POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent: All ☐ Part ☐

TECHNICIAN

None ☐ X ☒

Operations Completed: Hour: 2:00P.M. Day: 14 Month: 4 2008

Actual Plugging Report: THE WELL WAS PERFORATED AT 500' AND AT 200'. 1" PIPE

WAS RAN INTO THE 2" CASING TO 700'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL

CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE 1" PIPE WAS REMOVED.

DISPLACEMENT WAS FILLED FROM SURFACE. 21 SACKS OF CEMENT WERE PUMPED

INTO THIS WELL.

RECEIVED

KANSAS CORPORATION COMMISSION

MAY 19 2008


Remarks: (GPS SESSION POINT NO. 02) (THIS WAS WELL NO F-16A ON THE LEASE MAP.)

CONSERVATION DIVISION
WICHITA, KS

(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed:


TECHNICIAN