

3 023351

15-001-02401-00-00

To:

API NUMBER 20080046-029

STATE CORPORATION COMMISSION

SW,SE,SE 1/4 Sec/Twp/Rge S.14-T.26S.-R.18E.

Wichita State Office Bldg. - PLUGGING SECTION

394 feet from south section line

130 S. Market, Room 2078

1156 feet from east section line

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Lease/Well# LOCKHART NO. BB-14

Operator License # 100101

County ALLEN

Operator: STATE OF KANSAS

Well Total Depth 850 feet

Name & FEE FUND PLUGGING

Production Pipe: 2" Size Feet 850

Address

Surface Casing: 8" Size Feet 20'

AB oil well X Gas Well SWD Well/ Input Well

D & A

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE, LLC

Lic. #

30670

Address: 19245 FORD RD., CHANUTE, KS. 66720

Company to plug at: Hour: 8:00A.M. Day: 29 Month: 4 2008

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 850' THAT MAY HAVE

CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO PERFORATE

THE 2" CASING AND TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent: All Part

TECHNICIAN

None X

Operations Completed: Hour: 11:00A.M. Day: 29 Month: 4 2008

Actual Plugging Report: THE 2" CASING WAS PERFORATED AT 150' AND AT 380'.

1" PIPE WAS RAN INTO THE 2" CASING TO 690'. CEMENT WAS PUMPED INTO THE 1"

PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE 1" PIPE WAS RECEIVED

REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 40 SACKS OF CEMENT

KANSAS CORPORATION COMMISSION

WERE PUMPED INTO THIS WELL.

MAY 19 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: (GPS SESSION POINT NO. 29) (THIS WAS WELL NO BB-14 ON THE LEASE MAP.)

(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed:


TECHNICIAN