

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-205-19506-00-00
NW NW SW Sec/Twp/Rge Sec 10, T29S, R17E
2029 (GPS) feet from south section line
4908 (GPS) feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Lease/Well# Martin (Stich) GPS # STI-01

Operator: State Of Kansas Fee Fund

County Wilson

Well Total Depth 700 (est) feet

Name & Martin (Stich) Lease Project

Production Pipe: 2 Size Feet 700

Address _____

Surface Casing: NA Size Feet NA

AB oil well XXXXXXX Gas Well _____

SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: K-W Oil Well Service, Inc Lic. # 3097

Address: 19450 Ford Road, Chanute, Kansas 66720

Company to plug at: Hour: _____ Day: 29 Month: 11 2007

Plugging proposal received from: Sam Kepley

Company Name: K-W Oil Well Service, Inc Phone: 620-433-7730

Were: Wash well to TD and fill from btm to top with portland cement.

Plugging Proposal Received by: Alan M. Dunning

Plugging attended by Agent: All _____ Part _____ None XXXXXX

TECHNICIAN

Operations Completed: Hour: _____ Day: 29 Month: 11 2007

Actual Plugging Report: This well was an open bore hole with no surface pipe, but with a 2 inch

production string. Mr. Kepley set 4 ft of 12" surface pipe. A one inch cement string was washed down the

inside of the 2" to 700 ft. A one inch cement string was washed down the outside of the 2" pipe to 600 ft.

The well was plugged from btm to top thru these cement strings. A total of 201 sacks of portland cement

were used to plug well. The well was cut off below plow depth and the location restored.

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: Control # 20080015-001
(If additional description is necessary, use BACK of this form.)

MAR 21 2008

CONSERVATION DIVISION
WICHITA, KS

I did not observe this plugging.

RECEIVED
KANSAS CORPORATION COMMISSION

Alan M. Dunning
TECHNICIAN

MAR 21 2008

CONSERVATION DIVISION
WICHITA, KS