

To:
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-205-19508-00-00
NW NW SW Sec/Twp/Rge Sec 10, T29S, R17E
2398 (GPS) feet from south section line
4745 (GPS) feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101Lease/Well# Martin (Stich) GPS # STI-04County WilsonOperator: State Of Kansas Fee FundWell Total Depth 750 (est) feetName & Martin (Stich) Lease ProjectProduction Pipe: 3 Size Feet 750

Address _____

Surface Casing: 5 Size Feet NAAB oil well XXXXXXX Gas Well _____

SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: K-W Oil Well Service, IncLic. # 3097Address: 19450 Ford Road, Chanute, Kansas 66720Company to plug at: Hour: _____ Day: 21 Month: 12 2007Plugging proposal received from: Sam KepleyCompany Name: K-W Oil Well Service, Inc Phone: 620-433-7730Were: Wash well to TD and fill from btm to top with portland cement thru cement string.

Plugging Proposal Received by:

Alan M. DunningPlugging attended by Agent: All _____ Part _____ None XXXXXX

TECHNICIAN

Operations Completed: Hour: _____ Day: 21 Month: 12 2007

Actual Plugging Report: Mr. Kepley set 4 ft of new 8" surface pipe. The 3" production pipe was perforated at 250', 150', and 75'. A one inch cement string was lowered to 750' inside the 3". The well was plugged from btm to top thru this cement string. A total of 108 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 21 2008

Remarks: Control # 20080015-004CONSERVATION DIVISION
WICHITA, KS(If additional description is necessary, use BACK of this form.)

I did not observe this plugging.

Signed:

Alan M. Dunning
TECHNICIAN