

To:
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-205-19509-00-00
NW NW SW Sec/Twp/Rge Sec 10, T29S, R17E
2436 (GPS) feet from south section line
4663 (GPS) feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101Lease/Well# Martin (Stich) GPS # STI-05County WilsonOperator: State Of Kansas Fee FundWell Total Depth 600 (est) feetName & Martin (Stich) Lease ProjectProduction Pipe: 2 Size Feet 600

Address _____

Surface Casing: 6 Size Feet NA

AB oil well _____ Gas Well _____

SWD Well/ Input Well XXXXXX D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: K-W Oil Well Service, IncLic. # 3097Address: 19450 Ford Road, Chanute, Kansas 66720Company to plug at: Hour: _____ Day: 2 Month: 1 2008Plugging proposal received from: Sam KepleyCompany Name: K-W Oil Well Service, Inc Phone: 620-433-7730Were: Wash well to TD and fill from btm to top with portland cement thru cement string.

Plugging Proposal Received by: _____

Alan M. Dunning

TECHNICIAN

Plugging attended by Agent: All _____ Part XXXXXX None _____Operations Completed: Hour: _____ Day: 2 Month: 1 2008Actual Plugging Report: The 2" production string was washed down to 300' to prepare forperforations. The well was perforated at 250', 150', and 75'. A one inch cement string was washed down to600'. The well was plugged from btm to top thru this cement string. A total of 28 sacks of portland cementwere used to plug well. The well was cut off below plow depth and the location restored.

RECEIVED

KANSAS CORPORATION COMMISSION

MAR 31 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: Control # 20080015-005. This was an unpermitted injection well. No records could be found in District III files. (If additional description is necessary, use BACK of this form.)

I partially observed this plugging

Signed: _____

Alan M. Dunning
TECHNICIAN

PES