


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

15-163-04081-0000

### WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Rooks

County. Sec. 2 Twp. 10 Rge. (E) 20 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW NE NE

Lease Owner Francis Oil & Gas Company

Lease Name Wilson Well No. 2

Office Address 902 Palace Building Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed 5-30-50 19

Application for plugging filed 5-30-50 19

Application for plugging approved 5-30-50 19

Plugging commenced 5-30-50 19

Plugging completed 5-30-50 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3843' Feet

Show depth and thickness of all water, oil and gas formations.

#### OIL, GAS OR WATER RECORDS

#### CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	250'	Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud from 3843' to 250'. Bridge at 250' with 1 sack of hulls and 15 sacks of cement. Filled with mud from bridge at 250' to 35' then ran a bridge and 10 sacks of cement.

6-9-50  
JUN 9 1950  
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Francis Oil & Gas Co.

Address 902 Palace Building, Tulsa, Oklahoma

STATE OF KANSAS, COUNTY OF MONTGOMERY, ss.

FLOYD W. HILD (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me GBE VEEDER SUPPLY & DEVELOPMENT COMPANY

(Signature) Floyd W. Hild

P. O. Box 201, Cherryvale, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 5th day of June 19 50.


Edo Lawson Notary Public

My commission expires July 11, 1952.

PLUGGING  
FILE SEC 27-10-R-204  
BOOK PAGE 8 LINE 28

15-163-04081-0000

Veeder Supply & Dev'l. Co.



Cherryvale, Kansas

Drilled for Francis Oil & Gas Company Farm Wilson No. 2 Depth 3843'  
 Contractor Veeder Supply & Development Company Pipe Set 257' of 8-5/8" Csg. Cemented with 150 sx.  
 Location Northeast Sec. 2 Twp. 10S Range 20W  
 Commenced 5-18-50 Completed 5-30-50 County Rooks State Kansas

Surface Soil	0	30	30
Gravel	30	50	20
Sand Shale	50	170	120
Shale Gravel	170	240	70
Shale	240	252	12
Shale Shells	252	880	628
Sand Shale	880	1050	170
Shale	1050	1150	100
Sand Shale	1150	1425	275
Red Bed	1425	1635	210
Anhydrite	1635	1720	85
Red Bed Shale			
Shells	1720	1795	75
Red Bed	1795	1875	80
Salt Shale	1875	1935	60
Shale	1935	2040	105
Salt Shale	2040	2110	70
Shale Lime Shells	2110	2215	105
Lime Shale	2215	2360	145
Shale Shells	2360	2510	150
Lime Shale	2510	2565	55
Lime	2565	2630	65
Lime Shale	2630	2830	200
Shale Shells	2830	2870	40
Lime Shale	2870	2975	105
Shale Shells	2975	3145	170
Lime Shale	3145	3330	185
Lime	3330	3525	195
Lime Chert	3525	3605	80
Lime	3605	3785	180
Lime Chert	3785	3817	32
Chert	3817	3843	26
T.D.	3843'		

RECEIVED  
JUN 9 1950

AFFIDAVIT

JUN 9 1950

STATE OF KANSAS  
MONTGOMERY COUNTY SS:

FLOYD W. HILD, of lawful age, being duly and solemnly sworn on oath says;  
I am a resident of Cherryvale, Montgomery County, Kansas, and I hereby know  
and on oath state, that the above drilling log covering the Wilson #2 Well  
in Section 2-10S-20W, Rooks County, Kansas, is true and correct.  
Further affiant saith not.

THE VEEDER SUPPLY & DEVELOPMENT COMPANY

By Floyd W. Hild

Subscribed and sworn to before me this 1st day of June, 1950.

Loles Lawson  
Notary Public

My Commission Expires: July 11, 1952

PLUGGING  
FOR SEC 2 T 10 S R 20 W  
8000 PAUL & LINE 28

