


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

15-163-011460000

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Rooks _____ County: Sec. 2 Twp. 10S Rge. (E) 20 (W)
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines NW $\frac{1}{4}$ SE $\frac{1}{4}$ SE $\frac{1}{4}$
Lease Owner Barnett Oil Company
Lease Name Coddington Well No. 3
Office Address 417 First National Bank Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 13, 1952
Application for plugging filed February 13, 1952
Application for plugging approved February 13, 1952
Plugging commenced February 13, 1952
Plugging completed February 13, 1952
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production - - - - - 1952
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3860 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface Casing		-0-	145	8 5/8	145	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud from 3860 feet to 145 feet. Set wooden plug at 145 feet and filled casing with 1/2 sack of hulls and 15 sacks of cement to 98 feet. Filled casing with heavy mud from 98 feet to 40 feet. Set wooden plug at 40 feet and filled casing with 1/2 sack of hulls and 10 sacks of cement to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Barnett Oil Company
Address 417 First National Bank Building
Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
W. R. Hunter (employee of owner) or ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. R. Hunter
First Natl. Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 21st day of February, 1952
My commission expires Jan 18, 1956
Mahell E. Minor Notary Public.

PLUGGING
FILE SEC 2 T10 R20W
BOOK PAGE 44 LINE 41

RECEIVED
FEB 22 1952
DIVISION

15-163-01146-0000

BARNETT OIL COMPANY, ET AL

LOG OF CODDINGTON WELL NO. 3

NW¹/₄ SE¹/₄ SE¹/₄ SECTION 2-10S-20W, ROOKS COUNTY KANSAS

DATE COMMENCED: FEBRUARY 1, 1952

DATE COMPLETED: FEBRUARY 13, 1952

<u>Formation</u>	<u>From</u>	<u>To</u>	<u>Remarks</u>
Sand	-0-	20	
Shale	20	105	
Shale and Shells	105	1160	Set 8 5/8" 2 1/2" Surface Pipe at 145 Feet; cemented with 125 sacks of cement.
Sand	1160	1390	
Shale and Shells	1390	1668	
Anhydrite	1668	1705	
Shale and Shells	1705	2210	
Shale and Lime	2210	3395	
Lime	3395	3860	
Total Depth		3860	Dry and Abandoned.

