

15-163-30041-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County, Sec. 2 Twp. 10 Rge. 20 (E) W (W)

Location as "NE/CNW/SW" or footage from lines C W/2 NW SE
Lease Owner Leo J. Dreiling Oil Company RTKCC
Lease Name Coddington Well No. #1
Office Address Victoria, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed 6-9 19 65
Application for plugging filed 6-14 19 67
Application for plugging approved 6-14 19 67
Plugging commenced 7-22 19 67
Plugging completed 7-22 19 67
Reason for abandonment of well or producing formation Depleted

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production October 19 66
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Arbuckle Depth to top 3815 Bottom _____ Total Depth of Well 3836 Feet
3827
RTKCC
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	187	8 5/8"	X	
		0	3823	5 1/2"	X	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mixed 15 sack cement 28 sacks hulls, 85 sacks cement down 5 1/2" casing.
Shut in pressure 1100 lbs. Pumped 15 sacks cement down annulas

RECEIVED
STATE CORPORATION COMMISSION
7-31-67
JUL 31 1967

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leo J. Dreiling Oil Company
Address Victoria, Kansas 67671


STATE OF KANSAS, COUNTY OF ELLIS, ss.
I, Leo F. Dreiling (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling
Leo F. Dreiling, Route 2, Victoria, Kansas 67671
(Address)

SUBSCRIBED AND SWORN to before me this 28 th day of July, 19 67

My commission expires September 19, 1970

Joseph A. Hess
Joseph A. Hess Notary Public.



L. J. DREILING and SONS, Inc.
VICTORIA, KANSAS

WELL LOG

Company LEO J. DREILING OIL CO.
VICTORIA, KANSAS

Sec. 2 Twp. 10 Rng. 20

Farm Coddington No. # 1

Location C-W $\frac{1}{2}$ -N $\frac{1}{2}$ -SE $\frac{1}{4}$

Total Depth 3827'

County Rooks County

Comm. 6-2-65 Comp. 6-9-65

Elevation: 2240' D. F.
2243'
2238' G. R.

Contractor

Casing Record
187' 8-5/8"
3823'

Cement Record
100 sax common
125 salt saturated cmt.

Production:

Arbuckle

RECEIVED
STATE CONSERVATION COMMISSION
JUN 14 1965
CONSERVATION DIVISION
Wichita, Kansas

Figures Indicate Bottom of Formations

0'	80'	sand
80'	187'	shale
187'	711'	shale
711'	1170'	shale
1170'	1390'	sand
1390'	1705'	Red bed & shale
1705'	1711'	Anhy.
1711'	1744'	Anhy.
1744'	2060'	shale & shells
2060'	2273'	shale & shells
2273'	2330'	shale & lime
2330'	2498'	shale & lime
2498'	2644'	shale & lime
3644'	2892'	shale & lime
2892'	3015'	shale & lime
3015'	3280'	shale & lime
3280'	3404'	shale & lime
3405'	3495'	lime
3495'	3564'	lime
3564'	3620'	lime
3629'	3687'	lime
3687'	3704'	lime
3704'	3789'	lime
3789'	3808'	lime
3808'	3820'	Cong.
3820'	3827'	Arb.
3827'	T.D	

STATE OF KANSAS)
)ss
COUNTY OF ELLIS)

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Coddington # 1.

Leo F. Dreiling
LEO F. DREILING

Subscribed and sworn to before me this 12th June, 1965.

My commission expires: October 26, 1968

Elmer [Signature]
NOTARY PUBLIC