

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD #16
 K.A.R.-82-3-117

15-1163-00234-0000

API NUMBER None

LEASE NAME Wilson A

WELL NUMBER 1

4950 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 2 TWP. 10 SRGE. 20 (X) or (W)

COUNTY Rooks

Date Well Completed 4-2-49

Plugging Commenced 5-7-85

Plugging Completed 5-7-85

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Kaiser-Francis Oil Company

ADDRESS P. O. Box 21468 Tulsa, OK 74121-1468

PHONE# (918) 494-0000 OPERATORS LICENSE NO. 6568

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District 6, Hays, KS

Is ACO-1 filled? On old form if not, is well log attached? --

Producing Formation Arbuckle Depth to Top 3821 Bottom 3831 T.D. 3831

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	Oil	3821	31	8-5/8	219	-0-
				5-1/2	3821	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Spotted 40 sx cmt plug from 3831'-3463'. Spotted 110 sxs cmt from 1012'-Surf. Pumped 100 sxs cmt down csg annulus. Plugging complete.

(If additional description is necessary, use BACK of this STATE CORPORATION COMMISSION

Name of Plugging Contractor Kaiser-Francis Oil Company License No. 6568

Address P. O. Box 21468 Tulsa, OK 74121-1468

STATE OF Oklahoma COUNTY OF Tulsa

CONSERVATION DIVISION
 Wichita, Kansas

Drew Tyler (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Drew Tyler

(Address) P. O. Box 21468 Tulsa, OK 74121-1468


SUBSCRIBED AND SWORN TO before me this 23rd day of May, 19 85

Donna M. Knapp
 Notary Public

My Commission Expires: 11-22-86

Wilson #1

Veeder Supply & Dev'l. Co.



Cherryvale, Kansas

Drilled for Francis Oil & Gas, Inc. Farm Wilson No. #1 Depth 3825'
 Contractor Veeder Supply & Development Company Pipe 222½' of 8 5/8" Csg. cemented with 150 sacks.
 Location NE NE NE Sec. 2 Twp. 10S Range 10W
 Commenced 3-15-49 Completed 4-2-49 County Rooks State Kansas

Soil Clay	0	15	15	Top Arbuckle - 3822'
Sand Shells	15	130	115	Total Depth rotary table - 3824'
Shale	130	220	90	Pipe set at 3822½' rotary table which
Shale Shells	220	850	630	is 1½' off bottom.
Sand Shale	850	1375	525	
Shale Red Bed	1375	1690	315	
Salt Shale	1690	1750	60	
Shale Shells	1750	2195	445	
Shale Lime Shells	2195	2300	105	
Lime Shale	2300	3425	1125	
Lime	3425	3730	305	
Conglomerate Chert	3730	3823	93	
Arbuckle	3823	3825	2	
Total Depth	3825'			

AFFIDAVIT

STATE OF KANSAS
MONTGOMERY COUNTY SS:

EMMETT C. VEEDER, of lawful age, being duly and solemnly sworn on oath says; I am a resident of Cherryvale, Montgomery County, Kansas, and I hereby know and on oath state, that the above drilling log covering the Wilson #1 Well in Section 2-10S-10W, Rooks County, Kansas, is true and correct.
Further affiant saith not.

THE VEEDER SUPPLY & DEVELOPMENT COMPANY

By *Emmett C. Veeder*
President

Subscribed and sworn to before me this 5th day of April, 1949.

Lois Lawson
Notary Public

My Commission Expires: 7-11-52.

APR 1 1949