

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH


Locate well correctly on above  
Section Plat

Rooks County. Sec. 2 Twp. 10 Rge. 20 ~~XX~~ (W)  
Location as "NE/CNW/SE" or footage from lines SE/4  
Lease Owner Herman Geo. Kaiser  
Lease Name Wilson "A" Well No. 2  
Office Address 908 Palace Bldg. Tulsa, Okla.  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed Oct. 22, 1957 19  
Application for plugging filed Oct. 22, 1957 19  
Application for plugging approved Oct. 22, 1957 19  
Plugging commenced Oct. 22, 1957 19  
Plugging completed Oct. 22, 1957 19  
Reason for abandonment of well or producing formation well being drilled for salt water disposal well, unable to complete because struck iron in hole  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation Depth to top Bottom Total Depth of Well 1689 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set plug at 650 ft. ran 20 sacks cement; filled with mud to 210 ft.  
Set plug 210', ran 15 sacks cement. Ran sk. hulls and filled with mud to 40'. Set plug at 40'. Ran 10 sacks cement. Filled and cemented to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Veeder Supply and Development Co.  
Address Box 201, Cherryvale, Kansas

STATE OF Kansas, COUNTY OF Montgomery, ss.  
C. H. Woods (employee of owner) or (owner's representative) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. H. Woods  
Cherryvale, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 25th day of October, 19 57  
Ides Lawson  
My commission expires July 11, 1960 Notary Public.

PLUGGING  
FILE 2 T 10 R 20 W  
BOOK PAGE 57 LINE 10

15-163-04081-0001

Veeder Supply &amp; Dev'l. Co.

Cherryvale, Kansas

Herman Geo. Kaiser

Drilled for Francis Oil &amp; Gas Company Farm Wilson "A" No. 2 Depth 1689'

Contractor Veeder Supply &amp; Development Co. Pipe

Location SE/4 Sec. 2 Twp. 10 Range 20

Commenced 10-15-57 Completed 10-22-57 County Rooks State Kansas

Cement	0	70	70
Mud	70	120	50
Cement	120	200	80
Cavings	200	980	780
Shells, Shale & Sand	980	1165	185
Shale, sand, red bed	1165	1415	250
Phyrite	1415	1440	25
Sand, shale, red bed	1440	1545	105
Red bed, sand, phyrite, shale	1545	1655	110
Iron	1655	1689	34

AFFIDAVIT

STATE OF KANSAS )  
 Montgomery County) SS

C. H. Woods, of lawful age, being first duly sworn on oath, deposes and says:

THAT he has read the above log covering the Wilson "A" #2 well located in Section 2-10-20 Rooks County, Kansas, and that the same is true and correct. Further affiant saith not.

THE VEEDER SUPPLY AND DEVELOPMENT CO.

By C. H. Woods  
 C. H. Woods

Subscribed and sworn to before me this 25th day of October, 1957.

C. H. Woods  
 Notary Public

My commission expires July 11, 1960.

