

15-163-03069-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Rocks _____ County. Sec. 3 Twp. 10 Rge. 20 (E) _____ (W) _____

Location as "NE/CNW&SW&" or footage from lines NE SE NE 1/4

Lease Owner Francis Oil & Gas, Inc.

Lease Name Nutsch "B" Well No. 2

Office Address 905 Palace Bldg., Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) dry

Date well completed August 17 19 54

Application for plugging filed August 17 19 54

Application for plugging approved August 17 19 54

Plugging commenced August 17 19 54


Plugging completed August 17 19 54

Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Warren H. Horner

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3885 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	207	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

FILLED HOLE WITH HEAVY ROTARY MUD
TO 206', SET PLUG AND CEMENT WITH
20 SACKS CEMENT THROUGH DRILL PIPE.
MUDDING HOLE TO 40 FT. SET PLUG AND
TEN SACKS CEMENT AT THE SURFACE

RCVD
09-02-54

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor H 30, Inc.

Address 710 Petroleum Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick

L. C. Sponenberg (employee of contractor) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. C. Sponenberg
(Address) _____

SUBSCRIBED AND SWORN to before me this 20 day of August, 19 54

My commission expires February 13, 1956

Rose Lucey Notary Public.

PLUGGING
FILE SEC 3 T 10 R 20W
BOOK PAGE 52 LINE 28

15-163-03069-0000

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **Francis Oil & Gas, Inc.**

SEC. **3** T. **10S** R. **20W**

FARM **Hutsch B** NO. **2**

LOC. **NE SE NE**

TOTAL DEPTH **3885**

COUNTY **Stooks**
KANSAS


COMM. **8/7/54**

COMP. **8/17/54**

SHOT OR TREATED

CONTRACTOR **H-30, Inc.**

ISSUED



CASING

20	10	
15	8	207'
12	6	
13	5	

ELEVATION **2269 KB**

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

Surface Clay & Sand	95
Shale	210
Sand w/Shale streaks	970
Shale	1065
Sand, Shale & Shells	1765
Anhydrite	1800
Red Bed, Shale & Shells	2100
Shale, Shells & Salt	2275
Shale & Lime	3203
Shale & Lime - Broken	3317
Shale & Lime	3670
Lime	3707
Shale & Lime	3805
Shale, Lime & Chert	3865
Lime & Chert	3885

FORMATION TOPS (K.B. Mens.)

HEBNER	3521
TORONTO	3543
LANSING	3561
BASE KANSAS CITY	3779
SHALEY CONGLOMERATE	3829
CHERTY CONGLOMERATE	3845
RTD	3885

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

By *E.P. Spruill*

STATE OF KANSAS

SS:

COUNTY OF SEDGWICK

Subscribed and sworn to before me, a notary public, in and for said County and State this 20th day of August, 1954.

My Commission expires February 13, 1956.

RECEIVED Notary Public
STATE CORPORATION COMMISSION

SEP - 2 1954

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 3 T 10 R 20W
BOOK PAGE 52 LINE 28