

LEASE NAME Hall

WELL NUMBER # 2

TYPE OR PRINT
NOTICE: Fill out completely
and return to Coas. Div.
office within 30 days.

4290' Ft. from S Section Line

3960' Ft. from E Section Line

SEC. 4 TWP. 10 RGE. 20 (E) or (W)

COUNTY Rooks

LEASE OPERATOR N. F. Producers Inc.

ADDRESS 940 Wadsworth Ave, Suite 300
Lakewood, Colorado 80215

PHONE# (800) 525-3332 OPERATORS LICENSE NO. 4472

Date Well Completed 10-3-47

Character of Well oil

Plugging Commenced 8-8-01

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8-8-01

The plugging proposal was approved on 8-5-01 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? unknown If not, is well log attached? no

Producing Formation Arbuckle Depth to Top 3834' Bottom 3836' T.O. 3836'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface pipe		0	360	10"	360	none
Production pipe		0	3834	6"	3834	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, - from feet to feet each set
Could not clean out below 1040', drilling on fiberglass tubing. Acidize well with 250 gals 28% acid. Mix 180 sks cement 60/40 poz, 10% gel, then 160 sks cement with 700# hulls. Pull tubing, hook onto casing, mix 100 sks cement, hooked onto, back-side, could not pump into well. Top off casing with 15 sk cement.

Name of Plugging Contractor Allied Cementing License No. RECEIVED 9-11-01

Address P. O. Box 31, Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: N. F. Producers Inc.

STATE OF KANSAS COUNTY OF Ellis, ss.

Dean Dues (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Dean Dues


(Address) 1209 Haney Hays, KS

SUBSCRIBED AND SWORN TO before me this 7th day of September, 192001

Sandra Wilson
Notary Public

My Commission Expires: 1-19-2003

USE ONLY ONE SIDE OF EACH FORM



OR