


15-163-03071-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Rooks County. Sec. 4 Twp. 10 Rge. 20 (W)  
Location as "NE/CNW/SW" or footage from lines NE SW NW  
Lease Owner Mallonee Drilling & Oil Trading Associates  
Lease Name Hall-Miller Well No. 2  
Office Address 820 Union Center, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 8-4 19 57  
Application for plugging filed 8-14 19 57  
Application for plugging approved 8-14 19 57  
Plugging commenced 8-14 19 57  
Plugging completed 8-20 19 57  
Reason for abandonment of well or producing formation \_\_\_\_\_



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3832 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	281'	None
				5-1/2"	3829'	3386-1/2'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked the hole to 3832' and found it open. Filled w/sand to 3819' and ran 4 sacks of cement to 3790'. Pulled 5-1/2" casing (all but 18') on final 18 jts. Circulated casing w/mud, pulled 3 jts, pumped 35 sacks of cement through casing and pulled final 15 joints. Mudded the hole to 45', set a 10' rock bridge to 35' and ran 10 sacks of cement to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co., Inc.  
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
R. E. Mallonee (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
820 Union Center, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 26th day of August, 19 57

My commission expires 12-14-57

PLUGGING  
FILE SEC 4 T. 10 R. 20W  
BOOK PAGE 35 LINE 9

Notary Public  
**RECEIVED**  
STATE CORPORATION COMMISSION  
8-27-57  
**AUG 27 1957**  
CONSERVATION DIVISION  
Wichita, Kansas

**DRILLERS' LOG**  
 #2 Well - Miller  
 NE SW NW Section 4-10-20W  
 Rocks County, Kansas

**OWNER:** Oil Trading Associates & Mallicoa  
**CONTRACTOR:** Mallicoa Drilling Company, Inc. **COMMENCED:** 7-19-57  
**COMPLETED:** 8-4-57

FROM	TO	DESCRIPTION
0	70	Surface soil and sand
70	120	Sand
120	235	Shale and sand
235	201	Shale and cholla
201	635	Shale
635	925	Sand and shale
925	1450	Shale and cholla
1450	1500	Sand & red bed w/pyrite streaks
1500	1745	Shale and cholla
1745	1790	Anhydrite
1790	1995	Shale and cholla
1995	2045	Limo and shale
2045	2530	Limo
2530	2650	Limo and shale
2650	2794	Limo
2794	3010	Limo and shale
3010	3120	Shale and cholla
3120	3415	Limo and shale
3415	3032	Limo
3032		Rotary Total Depth

CASING RECORD

8-3/8" casing set at 201' with 145 sacks  
 common cement, 2 sacks CC. Cement  
 circulated.

5-1/2" casing set at 3029' with 60 sacks  
 common cement.

TOPS

Elevation		2240 K.S.
Anhydrite	1745	✓ 504
Hardner	2477	-- 1220
Leading K.C.	3015	- 1237
Conglomerate	3772	- 1520
Stempan	3004	- 1555
Asbestos	3020	-- 1579
R.F.D.	3032	-- 1563

Drill Stem Test #1, 3029 - 32  
 Open 1 hour, recovered 63' oil, 13' water,  
 SHP 223'

I hereby certify that to the best of my knowledge and belief, the above represents a true and accurate  
 Drillers' Log of the completed well.

*R. E. Mallicoa*  
 R. E. Mallicoa

State of Kansas )  
 County of Sedgewick )

Subscribed and sworn to before me this 04th day of August, 1957.

My commission expires 12-14-57

<b>PLUGGING</b>			
FILE	SEC. 4	T. 10	R. 20 W
BOOK	PAGE 35	LINE 9	

*Maria Jones*  
 Notary Public (Maria Jones)