

15-163-04084-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD Strike out upper line
when reporting plug-
ging off formations.

Rooks County, Sec. 4 Twp. 10S Rge. (E) 20 (W)
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW $\frac{1}{4}$ SE $\frac{1}{4}$ NE $\frac{1}{4}$
Lease Owner Heathman-Honaker Drilling Co., Inc.
Lease Name Glick Well No. 3
Office Address 509 Orpheum Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed 11-27-1948
Application for plugging filed 11-27-1948
Application for plugging approved 11-27-1948
Plugging commenced 11-27-1948
Plugging completed 11-27-1948
Reason for abandonment of well or producing formation dry hole



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Box 105, Hays, Kansas
Producing formation --- Depth to top --- Bottom --- Total Depth of Well 3900 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
none				Surface pipe 8-5/8 (10 pts.)		none pulled.
				201.65' cement w/125 sacks.		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from --- feet to --- feet for each plug set.

Filled hole with heavy mud to 200'; wooden plug placed @ 200'
15 sacks cement was mixed and dumped into hole. Hole filled
with heavy mud to within 30 feet of top of hole, wooden plug
placed @ 30' and 10 sacks cement put in. Surface pipe cut off 2 1/2'
below level of ground.

RECEIVED
12-4-48
DEC - 4 1948
STATE CORPORATION
KANSAS

(If additional description is necessary, use BACK of this sheet)


Correspondence regarding this well should be addressed to Heathman-Honaker Drilling Co., Inc.
Address 510 Orpheum Building
Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
H. D. Shreve (employee of owner) or operator of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-
described well as filed and that the same are true and correct. So help me God.

(Signature) *H. D. Shreve*
509-510 Orpheum Building, Wichita, Kansas
(Address)

Subscribed and sworn to before me this 3rd day of December, 1948.
My commission expires June 28, 1952.

D. Marjorie Matt
Notary Public.



22-2625 2-48-15M
PLUGGING
FILE SEC 4 T 10 R 20 W
BOOK PAGE 70 LINE 28

15-163-04084-0000

GLICK NO. 3 WELL

Location: C.NW/4 SE/4 NE/4 Sec.4-10S-20W
Rooks County, Kansas
Operator: Heathman-Honaker Drilling Co., Inc.
Contractor: Heathman-Honaker Drilling Co., Inc.
Casing Record: 204.65' (10 jts.) 8-5/8" surface casing cemented @ 202' w/125 sacks.

No oil string run.
Dry and abandoned 11-27-48

Date Spudded: 11-16-48
Total Depth: 3900'
Elevation: 2246 DF; 2248 KB

FORMATION TOPS

Anhydrite	1733 (+ 515)
Heebner	3492 (-1244)
Lansing	3534 (-1286)
Conglomerate shale	3792 (-1544)
Conglomerate chert	3809
Total Depth	3900 (-1652)

LOG

(Figures indicate bottom of formation)

Sand and shale	202	Lime and shale	2300
Shale	762	Shale lime	2595
Shale and shells	1565	Lime	2660
Shale, shells, sand	1733	Lime and shale	2978
Anhydrite	1771	Shale	3055
Shale shells	1780	Shale and lime	3159
Shale shells	1995	Shale	3284
Shale and lime	2200	Lime and shale	3534
Kansas City Lime		3578	
Lime shale		3807	
Congl. Chert		3847	
Conglomerate		3900	
Total Depth		3900'	

The undersigned, H. D. SHREVE of the HEATHMAN-HONAKER DRILLING CO., INC., hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above noted well as reflected by the Daily Drilling Reports.

HEATHMAN-HONAKER DRILLING CO., INC.

BY: H. D. Shreve
H. D. Shreve

Subscribed and sworn to before me
this 3rd day of December, 1948.

D. Marjorie Mott
Notary Public

My commission expires: June 28, 1952.

PLUGGING
FILE SEC 4 T 10 R 20W
BOOK PAGE 70 LINE 28