

LEASE NAME Hall

WELL NUMBER 4

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

4290 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 4 TWP. 10 RGE. 20 (E) or (W)

COUNTY Rooks, Kansas

Date Well Completed 5-27-49

Plugging Commenced 8-8-01

Plugging Completed 8-8-01

LEASE OPERATOR N.F. Producers, Inc.

ADDRESS 940 Wadsworth Avenue Suite 300

PHONE#( 800-525-3332 OPERATORS LICENSE NO. 4472

Character of Well Oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-5-01 (date)

by Herb Dienes (KCC District Agent's Name).

Is ACO-1 filed? Unkown If not, is well log attached? No

Producing Formation Arbuckle Depth to Top 3807 Bottom 3818 T.O. 3818

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface pipe		0	372	10"	372	none
Production string		0	3808	5 1/2"	3808	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set  
Run 2760' tubing, Allied Cementing mix 8 sks gel, then 50 sks cement with 200# hulls. Pull tubing to 2100' mixed 160 sks 60/40 poz, 10% gel. Circulated cement to pit. Pull tubing out of hole. Hooked onto 5 1/2" casing, pumped 15 sks. cement, max pressure 300#. Shut in 200#. Hook onto backside, pump 25 sks. cement, with 100#-hulls. Shut in pressure 350#. Perforstions - 2210', 1785', 975'

Name of Plugging Contractor Allied Cementing License No. \_\_\_\_\_

Address P.O. Box 31, Russell, Ks. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: N. F. Producers

STATE OF KANSAS COUNTY OF ELLIS, ss.

Dean Dienes (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Dean Dienes


(Address) 1209 Honey Hays, Ks.

SUBSCRIBED AND SWORN TO before me this 7<sup>th</sup> day of September, 2001

Sandra Wilson  
Notary Public

My Commission Expires: 1-19-2003

USE ONLY ONE SIDE OF EACH FORM



OR