


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Rooks County. Sec. 4 Twp. 10 Rge. 20 (E) (W) x
Location as "NE/CNWxSWx" or footage from lines NW SE/4
Lease Owner Okmar Oil Co.
Lease Name Glick Well No. #7
Office Address 820 Union National Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 11-30-63 19____
Plugging completed 12-3-63 19____
Reason for abandonment of well or producing formation _____
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3853' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Squeezed hole with 30 sacks jel and 50 sacks cement.
Mixed 45 sacks cement and pumped down 4 1/2" casing to fill to top of casing.
Mixed 15 sacks jel and 5 sacks cement and pumped down between 5 1/2" and 8 5/8" casing.

RECEIVED
STATE CORPORATION COMMISSION
12-5-63
DEC 5 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer, Sec.
Box 364, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 4 day of December, 19 63
24 October 1964
My commission expires _____
Sidney J. Miller
Notary Public.

15-163-02017-0000

Company: Okmar Oil Company
Contractor: Glenn R. Nye Drilling Company
Commenced: February 21, 1952
Completed: March 6, 1952

Farm: Glick #7
Location: ~~SW~~ NW SE Sec. 4-10-20
Rooks County, Kansas
Casing Record: 8 5/8" set at 175'
5 1/2" set at 3849'

(Figures below indicate bottoms)

surface soil & clay	40		
sand & gravel	145		
blue shale	175		
shale	392		
shale	520		
shale & sand	850		
sand	995		
sand	1030		
shale & shells	1100		
sand & shale	1210		
red bed	1220		
sand	1290		
sand & shale	1430		
red bed & shale	1575		
red bed & shale	1753		
anhydrite	1790		
shale & shells	1850		
shale & shells	1970		
shale	2070		
shale	2190		
shale & lime streaks	2238		
shale & lime	2330		
lime & shale	2440		
lime & shale	2517		
shale & lime	2605		
lime & shale	2667		
shale & lime	2725		
shale & lime	2805		
shale & lime	2880		
shale & lime	2960		
shale & lime	3035		
shale & lime	3070		
shale & lime	3160		
shale & lime	3225	Top Topeka	3288
shale & lime	3305		
shale & lime	3367		
lime & shale	3397		
lime & shale	3418		
lime & shale	3489	Top Heebner	3490
lime & shale	3535	Top K. C.	3530
lime & shale	3553		
shale & lime	3585		
lime	3620		
lime	3652		
lime	3688		
lime	3710		
lime & shale	3748	Base K. C.	3750
lime	3775	Chert Conglomerate	3793
conglomerate	3802		
conglomerate	3825	Simpson	3830
conglomerate	3830	Arbuckle	3848
simpson sand	3844		
simpson	3848		
arbuckle	3852	T. D.	

RECEIVED
STATE CORPORATION COMMISSION

DEC 12 1963

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

GLENN R. NYE DRILLING COMPANY

By Glenn R. Nye

STATE OF KANSAS)
) SS
Rooks County

Subscribed and sworn to before me, a Notary Public, in and for said County and State this 3rd day of May, 1952.

Commission Expires May 9, 1953.

John L. Spiess
Notary Public