

15-163-00323-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Rooks

County. Sec. 3 Twp 10S Rge. (E) 20 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW/4 NW/4 NE/4

Lease Owner Heathman Drilling Co., Inc., et al

~~XXXXXX~~ 509 Orpheum Building, Wichita, Kansas

~~XXXXXX~~ Lease Name: E. Nutsch #2 well

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed 4-28-1950

Application for plugging filed 4-28-1950

Application for plugging approved (date of written approval) 5-2-1950

Plugging commenced 4-28-1950

Plugging completed 4-28-1950

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production --- 19---

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Box 326, Hays, Kansas

Producing formation none Depth to top --- Bottom --- Total Depth of Well 393 1/2 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8" 28#	8 thd. (4 jts.)	
					cemented at 137' w/75 sacks	
					cement and 1 sack Cal. Chloride.	
						none pulled out.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

~~Hole filled with heavy mud, bottom hole plug set @ 130' and 42 sacks cement dumped on top, hole filled with heavy mud and cement. Surface casing then filled with cement, and pipe cut off 3' below level of ground.~~

Bottom hole plug set @ 130'; 42 sacks cement dumped on top, filling surface pipe with cement; pipe cut off 3' below level of ground.

5-5-50  
1950

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Heathman Drilling Co., Inc.

Address 509 Orpheum Building, Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick ss.

Robert F. Walters (employee of owner) ~~XXXXXX~~ of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert F. Walters



509 Orpheum Building, Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 3rd day of May, 1950.

My commission expires June 28, 1952.

D. Marjorie Matt  
Notary Public.



E. NUTSCH WELL #2

NW/4 NW/4 NE/4 Sec.3-10S-20W  
Rooks County, Kansas

Date Spudded: 4-17-50

Operator: Heathman Drilling Co., Inc.

Rotary Completion: 4-28-50

Contractor: Heathman Drilling Co., Inc.

Total Depth: 3934'

Surface Casing: 4 jts. (141') 8-5/8" 28# 8 thd.  
cemented @ 137' w/75 sacks  
Ash Grove and 1 sack Cal.Chloride.

Elevation: 2279 KB

Oil String: None run - D&amp;A 4-28-50

T O P S . K B

Anhydrite	1763 (+ 516)
Topeka	3316 (-1037)
Heebner	3523 (-1244)
Lansing-K.C.	3561 (-1282)
Base Kansas City	3791 (-1512)
Shale Conglomerate	3826 (-1547)
Chert Conglomerate	3856 (-1577)
Simpson	3888 (-1609)
Arbuckle	3902 (-1623)
Total Depth	3934'

LO G

(Figures indicate bottom of formation)

Sand and shale	0 to 137
Shale and sand	740
Shale	790
Sand and shale	910
Sand	1505
Shale	1515
Shale and shells	1700
Sand - shale	1763
Anhydrite	1800
Shale - shells	1835
Shale and shells	2020
Shale and shells	2375
Shale and lime	3320
Lime	3407
Lime - shale	3462
Lime	3523
Lime and shale	3579
Lime	3822
Lime and shale	3851
Chert shale	3906
Dolomite	3934
Total Depth	3934'

The undersigned, Robert F. Walters of the Heathman Drilling Co., Inc., hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above noted well as reflected by the Daily Drilling Reports.

*Robert F. Walters*  
Robert F. Walters

Subscribed and sworn to before  
me this 3rd day of May 1950.

*D. Margene Mott*  
Notary Public

My commission expires: June 28, 1952.

