

15-163-20336-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Rooks County. Sec. 3 Twp 10S Rge. 20 (E) X(W)
Location as "NE/CNWxSWx" or footage from lines SE SE NW
Lease Owner Okmar Oil Company
Lease Name Nutsch "B" Well No. 3
Office Address 1130 Wichita Plaza, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Dec. 14 1970
Application for plugging filed Dec. 14 1970
Application for plugging approved Dec. 14 1970
Plugging commenced Dec. 14 1970
Plugging completed Dec. 14 1970
Reason for abandonment of well or producing formation _____

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3819 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	248'	8-5/8"	248'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 720 feet.
Set first plug at 720 feet with 70 sacks cement.
Filled hole with heavy mud to 240 feet.
Set second plug at 240 feet with 20 sacks cement.
Filled hole with heavy mud at 40 feet.
Set top plug at 40 feet with 10 sacks cement.
Job complete at 11:30 A.M., 12-14-70

STATE RECEIVED
STATE CORPORATION COMMISSION
DEC 23 1970
CONSERVATION DIVISION
Wichita, Kansas
12-23-70

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Gabbert-Jones, Inc.
Address 830 Sutton Place, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
James S. Sutton, II (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James S. Sutton
830 Sutton Place, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN to before me this 22 day of December, 1970

My commission expires Feb. 1, 1972
Barbara J. Layton
Barbara J. Layton Notary Public.



GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

NUTSCH "B" #3
SE SE NW Section 3-10S-20W
Rooks County, Kansas

Commenced: December 7, 1970
Completed: December 14, 1970

OPERATOR: Okmar Oil Company

DEPTH		FORMATION	REMARKS
From	To		
0	250	Sand and shale	Ran 9 joints 8-5/8" casing, set @ 248' w/170 sacks cement.
250	842	Shale	
842	1450	Shale and sand	
1450	1732	Shale	
1732	1773	Anhydrite	
1773	2293	Shale	
2293	2455	Shale and shells	
2455	2598	Lime	
2598	2950	Lime and shale	
2950	3052	Lime	
3052	3422	Lime and shale	
3422	3510	Lime	
3510	3598	Lime and shale	
3598	3819	Lime	
3819	TD		Dry and abandoned.

RECEIVED
STATE CORPORATION COMMISSION
DEC 23 1970
CONSERVATION DIVISION
Wichita, Kansas

I, James S. Sutton, II, certify this is a correct copy of the Drillers' Log for the well drilled in the SE SE NW Section 3-10S-20W, Rooks County, Kansas, to the best of my knowledge and belief.

James S. Sutton II
James S. Sutton, II

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 21 day of December, 1970, personally appeared James S. Sutton, II, to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

Barbara J. Layton
Barbara J. Layton, Notary Public

My Commission Expires February 1, 1972.

