

KCC OIL/GAS REGULATORY OFFICE

Date 9/30/09

() New Situation

() Response to Request

() Follow-up

Operator license # 5210

Operator Leback Oil Co

15-055-22035-0000

Address P.O. Box 489

Location SW SESE, Sec 18, T 22S, R 33W

Hays, Kansas 67601

Lease Garden City Well # 3-18

County Finney

Operator phone number 620 938 2396

API # 15-055-22035

Reason for Investigation: Alternate II Cementing

8 5/8" 416' w/ 260sx, 4 1/2" 4845' w/ 135sx. No port collar or DV Tool

Problem: Btm of usable water @ 1100'. Production @ 9 ran 12-4-08

RBP set @ 1200'

T.D. = 4850'

Person(s) Contacted: _____

9/29/09 Findings: Log Tech perf 4 holes @ 1150'. Inj rate 1 1/3 BPM @ 500#.

Re perf @ 1101'. Inj rate 2 1/2 BPM @ 800#.

9/30/09 RU Allied. Inj rate dr to 3 BPM @ 800#. Pump 200sx 60/40 pa 8% gel & 50sx A+3% CC @ 600# to 800#. No blow or circulation up annulus. Run temp survey. Toe @ 980'

10/1/09 Perf @ 1000'. Allied pumped in 3 BPM @ 1000 psi.

Pump 100sx 60/40 pa 8% gel & 50sx A+3% CC. No blow or circulation up annulus

Perf @ 750'. Allied pumped 50sx A+3% CC @ 1500#. No blow or circ in annulus.

Perf @ 650'. Allied pumped 100sx 60/40 8% gel and 50sx A+3% CC.

Well circulated c.m.f. Circ 45sx to ph photos taken: _____

Action/Recommendations: Alternate II cementing complete.

RECEIVED

OCT 15 2009

KCC WICHITA

- () Lease Inspection
- () Complaint
- () Field Report

By Ken Schlick

PIR T II

Retain 1 copy Joint District Office.
Send one copy Conservation Division

- () RBDMS
- () TA program
- () KGS
- () T-1 database
- () District files
- () Courthouse

