

State of Kansas



15-051-30416-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
CONSERVATION DIVISION
1-16-1967
JAN 16 1967
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Michaels of Sage Drlg. Co. has this
date requested permission to plug the following described well:

Mr. Michaels guarantees payment of the plugging fee.

Operator's full Name: Circle Oil Company Inc.,

Complete Address: 500 Bitting Bldg., Wichita Kansas

Lease Name: Hall Well No. 1

Location: NW NE NE Sec. 1 Twp. 12 Rge. 17 (E)(W) X

County Ellis Total Depth 3675' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Michaels was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 540' and displace

25 sc cement thru drill pipe. Heavy mud to 300' set cementing plug and

displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sc hulls and 8 sc cement to base of cellar. Plug rat hole with

2 sc cement.

Very truly yours,

Leo Massey
Conservation Division Agent