



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. - 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 12-2-1968
 DEC 2 1968
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Lindenmuth
 Mr. ~~Ohl~~ of Chief Drlg. has this

date requested permission to plug the following described well:

Mr. Lindenmuth guarantees payment of the plugging fee.

Operator's full Name: Kathol Petr. Co. & Chief Drlg. Co.

Complete Address: 900 Sutton Place Wichita, Ks.

Lease Name: Rohleder Well No. 1

Location: SW NW NW Sec. 11 Twp. 12 Rge. 17 (E)(W) X

County: Ellis Total Depth 3670' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Lindenmuth was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 720' and displace
70 sc cement thru drill pipe. Heavy mud to 240' set cementing plug and
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole
with 2 sc cement.

Very truly yours,

Ken F. Massey
 Conservation Division Agent