

SIDE ONE

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

F Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

C Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # 6111 EXPIRATION DATE 6-30-83

OPERATOR N-B Company, Inc. API NO. 15-051-23,131-00-00

ADDRESS Box 506 COUNTY Ellis

Russell, KS 67665 FIELD Dist 57 North

** CONTACT PERSON Joe K. Branum PROD. FORMATION Marmaton
PHONE 913-483-5345

PURCHASER Koch Oil LEASE Nicholson "B"

ADDRESS Box 2239 WELL NO. 2

Wichita, KS 67201 WELL LOCATION SE SW SW

DRILLING Emphasis Oil Operations 330 Ft. from S Line and

CONTRACTOR ADDRESS Box 506 990 Ft. from W Line of

Russell, KS 67665 the SW (Qtr.) SEC16 TWP12S RGE 20W.

PLUGGING CONTRACTOR ADDRESS

WELL PLAT

(Office Use Only)

KCC
KGS
SWD/REP _____
PLG. _____

TOTAL DEPTH 3930 PBD

SPUD DATE 8-21-82 DATE COMPLETED 9-13-82

ELEV: GR 2222 DF KB 2227

DRILLED WITH (ROTARY) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE

Amount of surface pipe set and cemented 805 DV Tool Used? No

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Gas, Shut-in Gas, Dry, Disposal, Injection, Temporarily Abandoned, OWWO. Other

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.


A F F I D A V I T

Joe K. Branum, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

Joe K. Branum
(Name)

SUBSCRIBED AND SWORN TO BEFORE ME this 24th day of September, 19 82.



MY COMMISSION EXPIRES: February 6, 1984.

Glenda R. Tiffin
STATE CORPORATION COMMISSION
RECEIVED
09-27-1982
SEP 27 1982
CONSERVATION DIVISION
Wichita, Kansas

** The person who can be reached by phone regarding any questions concerning this information.

OPERATOR N-B Company, Inc. LEASE Nicholson "B" SEC. 16 TWP. 12S RGE. 20W

WELL NO. 2

FILL IN WELL INFORMATION AS REQUIRED:

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
<input checked="" type="checkbox"/> Check if no Drill Stem Tests Run.			Heebner	3494
			Toronto	3520
			Lansing	3534
			Base KC	3784
			Marmaton	3827
			Conglomerate	3862
			Arbuckle	3912
			TD	3930

If additional space is needed use Page 2, Side 2

Report of all strings set — surface, intermediate, production, etc. **CASING RECORD** (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8-5/8"	28	805	60/40 Poz	400	3% cc, 2% gel
Production	7-7/8"	4 1/2"	10 1/2	3916	ASC	125	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4	3/8 DP	3834-3840

Size	Setting depth	Packer set at
2-3/8"	3890	None

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
500 gal. 15% MSR	3834-3840
Nitro-Frac	3834-3840

Date of first production	Producing method (flowing, pumping, gas lift, etc.)	Gravity
9-15-82	Pumping	37

Estimated Production -I.P.	Oil	Gas	Water	Gas-oil ratio
	30 bbls.		% None	

Disposition of gas (vented, used on lease or sold) Perforations 3834-3840