

7-2

6 062177

API NUMBER 15-051-22432-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE, SEC. 8, T12 S, R20 W/Ex
2310 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4707

Lease Name Flax Well # 1

Operator: Carl Boxberger Oil Inc.
Name & Box 1604
Address Great Bend, Ks.

County Ellis 133.25

Well Total Depth 4017 to 4100 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 275

Abandoned Oil Well xx Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling Inc. License Number 6050

Address Box 347 Chase, Ks. 67524

Company to plug at: Hour: 9:00 am Day: 2 Month: July Year: 19 90

Plugging proposal received from Mike Kelso

(company name) Kelso Casing (phone) 913-938-2943

were: Order 250 sks 60/40 poz 8% gel 5 sks hulls.

RECEIVED
07-09-1990
JUL 9 1990

Plugging Proposal Received by Gilbert Scheck (TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 1:20am Day: 2 Month: July Year: 19 90

ACTUAL PLUGGING REPORT 8 5/8 set at 275 w/160 sks. 5 1/2 set at 4099 w/200sks.

Top perf at 3899'. Plugged bottom w/sand and 5sks cement to 3540'.

Shot pipe five times and recovered 2000'. Pumped in 8 5/8 25 sks cement followed w/5 sks hulls in 225 sks cement w/ 500 psi.

Remarks: By Allied additional description is necessary, use BACK of this form.)

INVOICED (did not observe this plugging.)

Signed Gilbert Scheck (TECHNICIAN)

DATE 7-17-90

INV. NO. 28588