

4-110063

2-24

08-23-63

01485-00-01

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-051-~~72-222~~

SW NE SW / 4 SEC. 08, 12 S, 20 W
1650 feet from S section line
3630 feet from E section line

Operator license# 4707

Lease: Schwab Well # 1

Operator: Carl Boxberger Oil, Inc.

County: Ellis 130.95

Address: P.O. Box 1604
Great Bend, Kansas 67530

Well total depth 4029 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 218 feet

Aband. oil well ☒ Gas well ☐ Input well ☐ SWD ☐ D & A ☐

Plugging contractor: Mike's Testing & Salvage, Inc. License# 31529

Address: P.O. Box 467 - Chase, Kansas 67524

Company to plug at: Hour: 3:00 P.M. Day: 24 Month: February Year: 1999

Plugging proposal received from: Mike Kelso

Company: Mike's Testing & Salvage, Inc. Phone: 316-938-2943

Were: Shoot 5 1/2" casing at 2000' and plug while pulling casing.
Ordered 230 sxs cement with 500# hulls.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All ☒ , Part ☐ , None ☐

Completed: Hour: 6:30 P.M. , Day: 24 , Month: February , Year: 1999

Actual plugging report: 8 5/8" set at 218' w/125 sxs. 5 1/2" casing at 4029' w/150 sxs.
Perfs at 3903' - 3924'; 3662' - 3668'; 3639' - 3644' and 3505' - 3515'. Sanded to 3500' with
5 sxs cement. Shot 5 1/2" at 2000' - could not pull. Tied to 5 1/2" casing and pumped 100 sxs
cement with 250# hulls. Shot 5 1/2" at 600' - pulled two joints. Tied back to 5 1/2" and pumped
50 sxs cement with 100# hulls. Pulled to 200' and circulated with 75 sxs cement. Pulled
remaining casing and wellbore was full. Total 225 sxs 60/40 pozmix - 10% gel and 350# hulls.
Dakota 645' - 945'. Anhy. 1679' - 1726'. Salt at 2189' - 2314'.

Remarks: Allied Cementing - Leons Tank Service.

Condition of casing(in hole): GOOD ☒ BAD ☐ Anhy.plug: YES ☒ NO ☐
Bottom plug(in place): YES ☐ , CALC ☐ , NO ☐ Dakota plug: YES ☒ , NO ☐
Plugged through TUBING ☐ , CASING ☒ . Elevation: 2295 GL

I did ☒ / did not ☐ observe the plugging.

INVOICED

DATE 3-10-99

INV. NO. 60690

RECEIVED
MAR - 3 1999
03-03-1999
CONSERVATION DIVISION
Wichita, Kansas

ROBERT R PRICE OPERATING INC.
P.O. BOX 45442

#1 SCHWAB "OWWO"

8-12-20W
SW NE SW

TULSA, OK 74145

CONTR RANGER DRILLING CO INC CTV ELLIS

GEOL _____ FIELD SWEET WILLIAM NW EXT (1/4 W)

E 2300 RB CM E8/15/81 CARD ISSUED 1/14/82 IP P 5 BOPD, TR W

+	+	+
+	+	+
+	+	+

API NOT ASSIGNED

MARM - INTV NA

LOG	TOPS	DEPTH	DATUM
*ANH		1679-	+ 621
B/ANH		1726	+ 574
TOP		3333	-1033
HEEB		3559	-1259
TOR		3580	-1280
LANS		3596	-1296
B/KC		3842	-1542
ET SC		3894	-1594
ARB		3984	-1684
TD		4002	-1702
* DRILLERS TOP			

OLD INFO: OPERATOR WAS RAINS &
WILLIAMSON, #1 SCHWAB, SPD 8/23/63,
SET 8" 218/125SX, COMP AS D&A/ARB,
9/5/63

DST (1) 3720-51/1' 10'M, SSO, SIP
1117-678#/30", FP 31-31#
DST (2) 3794-3823/90", 120'MW, SIP
1117-1132#/30", FP 25-77#

NEW INFO: RE-ENTERED EST 8/15/81, WSH
DWN TO OTD, SET PROD CSG, MICT - CO,
PF (MARM) INTV NA, FRAC'D, SWB DWN
W/GSO, POP, P 5 BOPD, TR W, 1/11/82,
NO OTHER INFO TO BE RELEASED AT PRESENT
WILL RELEASE INFO WHEN AVAILABLE

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

Kelso Casing Pulling

938-294

ROBERT R PRICE OPERATING INC

P.O. BOX 45442

TULSA, OK 74145

CONTR RANGER DRILLING CO. INC

#1 SCHWAB "OWWO"

8-12-20W
SW NE SW

CTY ELLIS

GEOL

FIELD SWEET WILLIAM NW EXT (1/2 W)

E 2300 RB CM E8/15/81 CARD ISSUED 1/14/82 IP P 5 BOPD, TR W

API NOT ASSIGNED

MARM - INTV NA

LOG	TOPS	DEPTH	DATUM
* ANH		1079-	+ 621
R/ANH		1226	+ 574
TOP		3333	-1033
IEEB		3554	-1259
TOR		3500	-1280
ANG		3596	-1296
E/KC		3842	-1542
ET SG		3894	-1594
WHI		3984	-1684
TD		4002	-1702
* DRILLERS TOP			

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

OLD INFO: OPERATOR WAS RAINS &
WILLIAMSON, #1 SCHWAB, SPD 8/23/63,
SET 8" 218/125SX, COMP AS O&A/ARB.
9/5/63

DST (1) 3720-51/1' 10'M, 550, SIP
1117-678#/30", FP 31-31#
DST (2) 3794-3823/90", 120'MW, SIP
1117-1132#/30", FP 25-77#

NEW INFO: RE-ENTERED EST 8/15/81, WCH
DOWN TO OTD, SET PROD CSG, MICT - CO,
PF (MARM) INTV NA, FRAC'D, SWF DOWN
W/GSO, POP, P 5 BOPD, TR W, 1/11/82,
NO OTHER INFO TO BE RELEASED AT PRESENT
WILL RELEASE INFO WHEN AVAILABLE

Carl Boxberger Oil Inc

Schwab #1

2/17/99

Perfs: 3903-24 - 43' new
3662-68
3639-44 3605-15
Surface 8 5/8 218' W/125
5 1/2 4049 4150

T.D 4030'

Top of Cement 3020'

RECEIVED
KANSAS CORP CONT
1999 FEB 18 A 11:31