

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-02064-00-00  
Spot: SWNWSE Sec/Twnshp/Rge: 11-10S-20W  
1650 feet from S Section Line, 2310 feet from E Section Line  
Lease/Unit Name: CROFFOOT B Well Number: 2  
County: ROOKS Total Vertical Depth: 3784 feet

Operator License No.: 32278  
Op Name: TENGASCO, INC.  
Address: 603 MAIN AVE., STE 500  
KNOXVILLE, TN 37902

Production Casing Size: 5.5 feet: 3775 UNKNOWN  
Surface Casing Size: 8.625 feet: 223 125 SX CMT

#122 98

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/29/2003 9:00 AM  
Plug Co. License No.: 32332 Plug Co. Name: FISCHER PIPE TESTING, INC.  
Proposal Rcvd. from: ED GLASSMAN Company: FISCHER PIPE TESTING, INC. Phone: (785) 726-3411

Proposed Plugging Method: Ordered 300 sxs cement and 850# hulls.  
Perforated at 2125' - 1700' - 975'.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 09/29/2003 12:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 223' w/125 wxs cement. 5 1/2" casing at 3775' w/unknown sxs cement.  
Ran tubing to 2125' - spotted 25 sxs cement with 150# hulls.  
Pulled tubing to 1700' - spotted 25 sxs cement with 150# hulls.  
Pulled tubing to 800' - spotted 25 sxs cement with 200# hulls.  
Pulled tubing to 450' - pumped 135 sxs cement - would not circulate.  
Pulled all tubing - shut down for one hour - top of cement static at 350'.  
Topped casing off with 100 sxs cement - casing stayed full.  
Tied to 8 5/8" x 5 1/2" annulus - squeezed 50 sxs cement with 250# hulls.  
Max. P.S.I. 50#. S.I.P. 50#.  
Total of 360 sxs 60/40 pozmix and 750# hulls.

RECEIVED  
10-03-03  
OCT 03 2003  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY. AMERICAN TANK SERVICE-WATER.

Plugged through: TBG

District: 04

Signed

Roger L. Moses  
(TECHNICIAN)

INVOICED

DATE

10-303

INV. NO.

2004060577

Form CP-2/3

OCT 02 2003

I O MILLER #9 GROFFOOT 'B' 11-10-20W  
 SW NW SE  
 Contr. VIRGINIA DRLG ROOKS County  
 E 2230 Comm. Comp. 12-14-56 IP 108 BOPD/KC

Tops	Depth	Datum	Casing
			8" 223
KC	3482	-1252	5" 3775
B/KC.	3702	-1472	SWB .9 BOPH, 5% WTR: PB 3750
CONG	3732	-1502	PERF 33/3691-96: SWB 1/2 BOPH
SIMP	3754	-1524	PERF 8/3679-81: 12/3672-75
			INC: ACID 4000: SWB 11-12 BO
			PH/4 HRS
ARB	3774	-1544	MARCOTTE
TD	3784	-1554	

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS

+	+	+
+	+	+
+	+	+