

6 040577

15-1003-03645-0000

D4372

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-
A/D SE NE
SE, SEC. 11, T. 10 S, R. 20 (W/B)

990 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7168

Lease Name Croffoot Well # 1-C-5 SWD

Operator: I.O. Miller

County Rooks 138.13

Name & Address P.O. Box 124

Well Total Depth 4250 feet

Ellis, Kansas

Conductor Pipe: Size - feet -

67637

Surface Casing: Size 8 5/8 feet 205' w/125

Abandoned Oil Well - Gas Well - Input Well - SWD Well X D&A -

Other well as hereinafter indicated -

Plugging Contractor Allied Contg. License Number -

Address Russell, KS

Company to plug at: Hour: 2:30 Day: 14 Month: 3 Year: 19 86

Plugging proposal received from Paul Bawman - Denville Clark

(company name) I.O. Miller (phone) -

were: 5 1/2" casing @ 3850' w/ 85 sv cont.

Bad csg in hole - attempted to run try to only. Ran tapered mill to 800' - mill hanging up - pulled mill - started to re-enter w/ mill - hung up at 90' - pulled mill - bad @ 30' of csg and 2 csg collars on top of mill - the entire csg collapsed @ 90' - hole taking fluid. Decided best to plug from S.P.

Plugging Proposal Received by Dennis Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part - None -

Operations Completed: Hour: 2:30 pm Day: 14 Month: 3 Year: 19 86

ACTUAL PLUGGING REPORT Hooked up to 8 5/8" S.P. -

Pumped in 320 sv 6 3/4 ppg 100 gal w/ 4# flocc - M.P.X. 900# P.S.I.

Shut-in 300# P.S.I.

RECEIVED
STATE CORPORATION COMMISSION

3-24-86
MAR 24 1986

CONSERVATION DIVISION
Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED
(If additional description is necessary, use BACK of this form.)
observe this plugging.

DATE MAR 25 1986

Signed Dennis Hamel (TECHNICIAN)

INV. NO. 13139

3-14