

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-02061-00-00
Spot: NENWSE Sec/Twnshp/Rge: 11-10S-20W
2310 feet from S Section Line, 1650 feet from E Section Line
Lease/Unit Name: CROFFOOT B Well Number: 5
County: ROOKS Total Vertical Depth: 3812 feet

Operator License No.: 32278
Op Name: TENGASCO, INC.
Address: 603 MAIN AVE., STE 500
KNOXVILLE, TN 37902

Production Casing Size: 5.5 feet: 3802 UNKNOWN
Surface Casing Size: 8.625 feet: 218 125 SX CMT

#123⁸⁹

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/29/2003 12:15 PM
Plug Co. License No.: 32332 Plug Co. Name: FISCHER PIPE TESTING, INC.
Proposal Rcvd. from: ED GLASSMAN Company: FISCHER PIPE TESTING, INC. Phone: (785) 726-3411

Proposed Plugging Method: Ordered 300 sxs cement and 700# hulls.
Perforated at 2125' - 1700' - 975'.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/29/2003 4:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 218' w/125 sxs cement. 5 1/2" casing at 3802' w/unknown sxs cement.
Ran tubing to 2125' - spotted 25 sxs cement with 150# hulls.
Pulled tubing to 1700' - spotted 25 sxs cement with 150# hulls.
Pulled tubing to 800' - spotted 25 sxs cement with 200# hulls.
Pulled tubing to 400' - circulated with 30 sxs cement.
Pulled all tubing - squeezed 25 sxs cement to 450#. Blew casing apart - cement stayed at top of casing.
Tied to 8 5/8" x 5 1/2" annulus - squeezed 50 sxs cement with 250# hulls.
Max. P.S.I. 200#. S.I.P. 200#.
Total of 180 sxs 60/40 pozmix - 10% gel - 750# hulls.

RECEIVED
10-3-03
OCT 03 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY. AMERICAN TANK SERVICE-WATER.

Plugged through: TBG

District: 04

Signed

Rogw L. Moses
(TECHNICIAN)

INVOICED

DATE 10-3-03

INV. NO. 2004060577

I O MILLER

#5 CROFOOT 'B'

11-10-20W
NE NW SE

Contr. VIRGINIA DRLG ROKKS County


E 2229^{RB} Comm. Comp. 11-4-55 IP 77 BOPD
PERM PMPG

Tops	Depth	Datum
HEEB	3444	-1215
TOR	3469	-1240
DOUG	3478	-1249
KC	3483	-1254
CONG	3739	-1510
SIMP	3763	-1534
REW ARB	3784	-1555
SOL ARB	3801	-1572
TD	3812	-1583

Casing
5" 3802

CO 3806: DD 3812: ACID 1000
5 BOPH

MARCOTTE POOL



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS