

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-02082-00-01
Spot: NWSESW Sec/Twnshp/Rge: 12-10S-20W
990 feet from S Section Line, 3630 feet from E Section Line
Lease/Unit Name: SUTOR "B" Well Number: 2
County: ROOKS Total Vertical Depth: 3749 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

Conductor Pipe: Size feet: \$ 121.84
Surface Casing: Size 8.625 feet: 1623
Production: Size 5.5 feet: 3747
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 02/05/2001 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTY ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2537

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 10% gel - 300# hulls.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 02/05/2001 12:30 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

R.U. casing pullers shot casing off at 2410' - pulled to 2150'.
R.U. Cementers spotted 150 sxs cement with 300# hulls.
Pulled casing to 1650'.
Spotted 40 sxs cement with 100# hulls - Pulled casing to 950'.
Spotted 40 sxs cement with 100# hulls - pulled casing to 200'.
Spotted 45 sxs cement to circulate at surface.
Pulled balance of casing with cement in cellar.
Job complete.

INVOICED
DATE 03-08-2001
WV. NO. 2001061451

RECEIVED
STATE CORPORATION COMMISSION

2-14-01
FEB 14 2001

CONSERVATION DIVISION

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

ND


Signed

Dennis L. Hamel

(TECHNICIAN)

"B"

STATE	KANS	COUNTY	ROOKS	OWWO	12-10S-20W
FIELD	MARCOTTE (MULTIPAY)				NW SE SW
OPER	TEX-CON O&G			990FSL	3630FEEL SEC
WELL	2 SUTOR "B"			WELL CLASS	DO
API	15-163-02082-0001			STATUS	OIL-WO
SPUD	08/18/1990			COMP	08/22/1990
DTD	3749	DE	FTD	PBTD	3686
			ARBUCKLE		



LOC Petroleum Information Corporation

IP IPP 5 BOPD 110 BW EL: 2200 KB 2194 GR
 PROD ZONE: LSG-KANS CITY 3580-3656 GROSS
 FIRST REPORT & COMPLETION

TBGS: 2 7/8 @ 3673

OWWO: OLD INFO: FORMERLY SOHIO PETROLEUM 2 SUTOR "B". SPUD 5/7/50. 8 @ 1623
 W/CMT, 5 @ 3747 W/CMT. LOG TOPS: LANSING 3450, PENN CONGL 3691,
 ARBUCKLE 3745. OTD 3749. COMP 6/23/50. IP DRAW DOWN 3000 BOPD.
 PROD ZONE: ARBUCKLE 3747-3749. OPENHOLE.

NEW: BRPG @ 3686

PERFS: LANSING-KANSAS CITY PERF W/ 2/FT 3580-3656 GROSS
 3580-3582 3586-3590 3600-3606 3615-3620
 3622-3626 3634-3642 3650-3656
 ACID 3000 GALS 15% HCL

8 5/8 1623
 5 1/2 3747

OPER ADDRESS: 9401 SOUTHWEST FRWY, HOUSTON, TX 77074