

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-02077-00-01
Spot: SENESE Sec/Twnshp/Rge: 12-10S-20W
1650 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: EARL SUTOR Well Number: 7
County: ROOKS Total Vertical Depth: 3764 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

Conductor Pipe: Size feet: # 122.33
Surface Casing: Size 8.625 feet: 1655 683 SX CMT
Production: Size 5.5 feet: 3762 100 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/23/2001 2:00 PM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTY ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2537

Proposed Plugging Method: Ordered 270 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: HERB DEINES
Date/Time Plugging Completed: 01/23/2001 4:30 PM

Witness Type: Plugging Operations 100% Witnessed (Complete)
KCC Agent: DENNIS HAMEL

Actual Plugging Report:

R.U. casing pullers - attempt stritch - casing parted at 1600'.
Spotted 125 sxs with 300# hulls at 1600'.
Pulled casing to 900' - spotted 40 sxs cement with 100# hulls.
Pulled casing to 400' - spotted 40 sxs cement with 100# hulls.
Pulled casing to 180' - spotted 75 sxs cement to circulated to surface.
Pulled balance of casing with cement in cellar.
Job complete.

INVOICED
DATE 03-08-2001
VV. NO. 2001061452

RECEIVED
STATE CORPORATION COMMISSION
2-14-01
FEB 14 2001

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

CONSERVATION DIVISION
WICHITA, KANSAS

District: 04

HD

Signed Dennis L. Hamel
(TECHNICIAN)

GULF OIL CORPORATION

#7

SUTOR

12-10-20W
SE NE SE

22

Encl

Contr. HERNDON DRILLING COMPANY

ROOKS

County

E 2227

Comm.

Comp.

1-12-51

IP

3000 BOPD

DRAW DOWN

Tops	Depth	Datum
ANH	1649	+ 278
HEEB	3424	- 1197
LANS	3461	- 1234
B/KC	3678	- 1451
CONG	3703	- 1476
VIO	3725	- 1498
SIMP	3738	- 1511
ARB	3761	- 1534
T.D.	3764	- 1537

Casing

8" 1655
5" 3762

DP 3764
SWB 77 80/4 HRS
ACID 500
SWB 96 80/2 HRS

BERLAND POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS