

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

0001

API Well Number: 15-163-19009-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 12-10S-20W
330 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: EARL SUTOR Well Number: 2
County: ROOKS Total Vertical Depth: 3776 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 1648 625 sx cmt \$122.72
Production: Size 5.5 feet: 3773 100 sx cmt
Liner: Size feet:

Well Type: EOR UIC Docket No: E26024.1 Date/Time to Plug: 02/01/2001 8:00 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTY ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2537

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: HERB DEINES
Date/Time Plugging Completed: 02/01/2001 10:00 AM

WitnessType: Plugging Operations 100% Witnessed (Complete)
KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Shot 5 1/2" casing off at 2510' - pulled casing to 2158'.
R.U. Cementers spotted 150 sxs cement plus 300# hulls.
Pulled casing to 1650' - spotted 40 sxs cement plus 100# hulls.
Pulled casing to 942' - spotted 40 sxs cement plus 100# hulls.
Pulled casing to 200' - spotted 45+ sxs cement to circulate at surface.
Pulled balance of casing with cement in cellar.
Job complete.

INVOICED
03-08-2001
INV. NO. 2001061452

RECEIVED
STATE CORPORATION COMMISSION
2-14-01
FEB 14 2001
CONSERVATION DIVISION
WICHITA, KANSAS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

ND

Signed Dennis L. Hamel
(TECHNICIAN)

Eanl

GULF OIL CORP #2 SUTOR 12-10-20W 22
SW SW SE

Contr. CORBETT-BARBOUR DRILLING CO. ROOKS County

E 2222 Comm. 2-27-50 Comp. 4-21-50 IP. 451 BOPD
PHY POT

Tops	Depth	Datum
ANH	1636	+ 586
HEEB	3433	-1211
LANS	3473	-1251
GONG	3710	-1488
SIMP	3752	-1530
ARB	3772	-1550
TD	3776	-1554

Casing

8" 1648 DP 3776: 20 GOPH:
5" 3773 ACID 500: SWB 165 BO/
15 HRS.

BERLAND POOL

+	+	+
+	+	+
+	+	+

8 5/8 1648
5 1/2 3773

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS