

10-26

69  
R

4- 060269

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-163-23.184 -0000

NE NE NW /4 SEC. 12, 10 S, 20 W  
330 feet from S section line  
2970 feet from E' section line

Operator license# 3613 Lease Desbien well # 10

Operator: Hallwood Petroleum, Inc. County Rooks

Address: 4582 S. Ulster St. Well total depth 3898 feet <sup>126.68</sup>  
Pkwy. #1700 Conductor Pipe: 0 inch @ 0 feet  
Denver, Colorado 80237 Surface pipe 8 5/8 Inch @ \_\_\_\_\_ feet

Aband. oil well \_\_, Gas well \_\_, Input well \_\_, SWD \_\_, D & A X

Plugging contractor: Lobo Drilling Company License# 5929

Address: Great Bend, Kansas 67530-0877

Company to plug at: Hour: 12:00A.M Day: 26 Month: October Year: 91

Plugging proposal received from: Irvin Neighbors

Company: Lobo Drilling Company Phone: 316-792-7476

Were: Order 225 sxs. 60/40 posmix - 6% gel. - 1/4# flocele per sx.  
Space all plugs with heavy drilling mud through drill pipe.


Plugging Proposal Received by: Herb Deines  
Plugging operations attended by agent? All[ ], Part[ ], None[ X ]

Completed: Hour: 12:00A.M, Day: 26, Month: October, Year: 91

Actual plugging report:  
1st. plug at 3807' with 25 sxs. - Arbuckle 3817'.  
2nd. plug at 1675' with 25 sxs. - Anhydrite 1658' - 1682'.  
3rd. plug at 925' with 100 sxs. - Dakota 625' - 925'.  
4th. plug at 270' with 40 sxs. - Surface pipe to 218'.  
5th. plug at 40' with 10 sxs.  
Rathole with 15 sxs.  
Mousehole with 10 sxs.

Remarks: Halliburton Cementing.

I did  and not  observe the plugging.



**INVOICED**  
DATE 12-5-91  
INV. NO. 33943  
10-26 JAN 28 1992

*Herb S.*

(agent)  
Form CP-2/3

RECEIVED  
STATE CORPORATION COMMISSION  
11-18-91  
NOV 18 1991  
CONSERVATION DIVISION  
Wichita, Kansas