

6 041121

12-29

163-03295-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- ~~167-95-002~~  
SE SE NE, SEC. 12, T 10 S, R 20 (W/EXX)

TECHNICIAN'S PLUGGING REPORT

Operator License # 6854

2970 feet from S section line  
330 feet from E section line

Operator: B. P. Exploration Inc.  
Name & Address: Box 37  
Gorham, Ks. 67640

Lease Name Desbien Well # 5  
County Rooks 124.28

Well Total Depth 3827 feet

Conductor Pipe: Size - feet -

Surface Casing: Size 8 5/8 feet 346' w/20 sks cement

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton Cementing License Number

Address Hays, Ks.

Company to plug at: Hour: 8:00 AM Day: 29 Month: Nov Year: 19 89

Plugging proposal received from Joel Stull

(company name) B. P. Exploration (phone)

were: 5 1/2" casing set at 3774' w/150 sks cement; 3 1/2" liner 3766 - 3822;

perf at 3780 - 84; hole in casing, sq in 1983 at 1640 - 1703 w/175 sks.

Dakota sq in 1951' w/650 sks cement interval N.A.

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 10:00AM Day: 29 Month: Dec Year: 19 89

ACTUAL PLUGGING REPORT Set EZSV at 1750'; Ran tubing to 1750' stung into EZSV

sq 175 sks cement to plug bottom w/600# psi, sting out and pumped 116 add sks cement to 200'  
Perf dakota at 950'; pumped 15 sks to sq at 500#; Hooked up to 8 5/8" s.p. Pumped in 105 sks  
cement w/max psi 350#. S.T. 150#.

RECEIVED  
STATE CORPORATION COMMISSION  
1-17-90  
JAN 17 1990

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED  
DATE JAN 24 1990

Signed Dennis L. Hamel (TECHNICIAN)

Dennis L. Hamel