

4-041779

15-163-00300-0000

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

7-16

API Number: 15- - 5-18-51

NW NW NW /4 SEC. 12 , 10 S, 20 W  
330 feet from N section line  
330 feet from W section line

Operator license# 3113  
Operator: Hallwood Petroleum, Inc.  
Address: 4582 S. Ulster St. Pkwy.  
Suite #1700  
Denver, Colorado 80237

Lease: C Desbien Well # 3  
County: Rooks  
Well total depth 3812 <sup>123.89</sup> feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 10 3/4 Inch @ 341 feet  
w/250 sxs.

Aband. oil well X, Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD \_\_\_\_\_, D & A \_\_\_\_\_

Plugging contractor: Allied Cementing License# \_\_\_\_\_

Address: Russell, Kansas 67665

Company to plug at: Hour: 8:30 A.M. Day: 16 Month: July Year 1996

Plugging proposal received from: Laurin Herl

Company: Hallwood Petroleum, Inc. Phone: 913-434-7687

Were: 5 1/2" casing set at 3770' w/200 sxs cement. Perf. at 3521' - 3672'.  
Ordered 325 sxs. 60/40 pozmix -10% gel - with 1/4# F.C. plus 1000# hulls and 13 sxs gel.  
Salt at 2115' - Anhy. at 1670' - B.S.P. at 375'. Perforated casing 07-15-96. Well squeezed  
at 985' with N.A. cement circulated.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[ X ], Part[ ], None[ ]

Completed: Hour: 12:00 P.M., Day: 16, Month: July, Year: 1996

Actual plugging report: R.I.H. with tubing 3500' - spotted 13 sxs gel, followed with 50 sxs  
cement with 300# hulls. Pulled tubing to 2100'. Spotted 75 sxs cement with 300# hulls.  
Pulled to 1100'. Spotted 75 sxs cement with 200# hulls to circulated at surface. P.O.O.H.  
with tubing. Squeezed casing with 45+ sxs cement. Max. P.S.I. 800#. Pumped down S.P. with  
5 sxs cement. Max. P.S.I. 500#. S.I.P. 500#.

RECEIVED  
KANSAS CORPORATION COMMISSION

7-24-96

JUL 24 1996

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD \_\_\_\_\_  
Bottom plug(in place): YES X, CALC \_\_\_\_\_, NO \_\_\_\_\_  
Plugged through TUBING X, CASING \_\_\_\_\_  
Anhy. plug: YES X NO \_\_\_\_\_  
Dakota plug: YES X, NO \_\_\_\_\_  
Elevation: \_\_\_\_\_ GL

I did[ X ] / did not[ ] observe the plugging.

Dennis L. Hamel  
(agent)

Form CP-2/3

INVOICED

DATE 7-25-96

NO. 46111