

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-02085-00-01
Spot: CSENWSW Sec/Twnshp/Rge: 12-10S-20W
1650 feet from S Section Line, 4290 feet from E Section Line
Lease/Unit Name: SUTOR B Well Number: 5
County: ROOKS Total Vertical Depth: 3766 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 1615 800 SX CMT \$122.40
Production: Size 5.5 feet: 3763 150 SX CMT
Liner: Size feet:

Well Type: EOR UIC Docket No: E20403.1 Date/Time to Plug: 02/06/2001 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTY ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2537

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 10% gel - 500# hulls.
Plug bottom with sand to 3500' plus 5 sxs cement on sand.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 02/06/2001 4:00 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Shot casing off at 2510'. Pulled casing to 2150'.
R.U. Cementers - spotted 150 sxs 60/40 pozmix - 300# hulls mixed in cement.
Pulled casing to 1650' - spotted 40 sxs cement - 100# hulls in cement.
Pulled casing to 950' - spotted 40 sxs cement - plus 100# hulls in cement.
Pulled casing to 200' - spotted 45 sxs cement to circulate at surface.
Pulled casing with cement in cellar.
Job complete.

INVOICED
DATE 03-08-2001
INVOICE NO. 2001061451

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Dennis L. Hamel
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
2-14-01
FEB 14 2001

CONSERVATION DIVISION
WICHITA, KANSAS

FEB 12 2001

" B "

SOHIO PETROLEUM CORP. #5 SUTOR B 12-10-20W 22
SE NW SW


Contr. R. W. RINE DRILLING COMPANY ROOKS County

E 2193 Comm. 10-28-50 Comp. 12-8-50 IP 97 BOPD

Tops	Depth	Datum
ANH	1610	+ 583
TOP	3208	- 1015
HEEB	3418	- 1225
LANS	3456	- 1263
CONG	3691	- 1498
ARB	3762	- 1569
T.D.	3767	- 1574

Casing
8" 1650 DST 3533-56, 1 HR,
5" 3763 30' MUD & WTR
DST 3626-66, 1 HR,
165' HEAVY OIL CUT MUD
DP 3767: ACID 1000
SWB 4 BOPH

BERLAND POOL



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS