

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-19010-00-00
Spot: NWSWSE Sec/Twnshp/Rge: 12-10S-20W
990 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: EARL SUTOR Well Number: 3
County: ROOKS Total Vertical Depth: 3773 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

Conductor Pipe: Size feet: \$122.62
Surface Casing: Size 8.625 feet: 1654 675 SX CMT
Production: Size 5.5 feet: 3766 100 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 02/01/2001 1:00 PM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTY ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2537

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: HERB DEINES

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 02/01/2001 3:00 PM

KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Shot 5 1/2" casing at 2720' - attempt to pull the same - casing parted at 145' - pulled to surface.
Decided to plug from top, took flow rate of 6bbls. per minute at 500#. Waited on cement.
R.U. Cementers to 8 5/8" S.P. and squeezed with 350 sxs cement with 500# hulls mixed in cement.
Max. P.S.I. 1000#. S.I.P. 500#.

Note: Top of 5 1/2" casing fish left in hole at 145'.
Calculated 8 5/8" - 5 1/2" casing cemented from surface to 1750'.

INVOICED
DATE 03-08-2001
NO. 2001061452

RECEIVED
STATE CORPORATION COMMISSION
2-14-01
FEB 14 2001

Remarks: ALLIED CEMENTING COMPANY

CONSERVATION DIVISION
Wichita, Kansas

Plugged through: CSG

District: 04

Signed Dennis L. Hamel
(TECHNICIAN)

FEB 07 2001

Foot

12-10-20W 22
NW SW SE

GULF OIL CORPORATION

#3 SUTOR


Contr. _____ ROOKS County

E 2227 Comm. 7-1-50 Comp. 8-18-50 IP 3,000 BOPD
DRAW DOWN

Tops	Depth	Datum
ANH	1649	+578
HEEB	3435	
LANS	3474	-1247
ARB	3765	-1538
T.D.	3773	

Casing
 8" 1654
 5" 3766
 DST 3623-53, 25
 MIN, REC 450'
 GAS & OIL CUT MUD:
 DD 3773: SWB 116
 BO/4 HRS: ACID 500
 SWB 160 BO/4 HRS

BERLAND POOL



8 3/8 1654
5' 3766

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS