

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-22502-00-00  
Spot: NWSEWNWNE Sec/Twnshp/Rge: 12-10S-20W  
4595 feet from N Section Line, 1665 feet from W Section Line  
Lease/Unit Name: DESBIEN Well Number: 9  
County: ROOKS Total Vertical Depth: 4133 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 8100 E. 22ND N. BLDG. 300  
WICHITA, KS 67226

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 282 170 SX CMT  
Production: Size 5.5 feet: 3865 275 SX CMT  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 03/27/2001 12:00 PM  
Plug Co. License No.: 31909 Plug Co. Name: STULL, JOEL  
Proposal Rcvd. from: JOEL STULL Company: STULL, JOEL Phone: (785) 885-4222

Proposed D.V. at 1500' with 350 sxs.  
Plugging Perfs 3470' - 3682'.  
Method: Ordered 225 sxs 60/40 pozmix - 10% gel plus 500# hulls and 15 sxs gel.

134.32

Plugging Proposal Received By: DENNIS HAMEL  
Date/Time Plugging Completed: 03/27/2001 2:00 PM

Witness Type: Plugging Operations 100% Witnessed (Complete)  
KCC Agent: DENNIS HAMEL

Actual Plugging Report:

R.I.H. with tubing to 3600' - spotted 50 sxs cement with 300# hulls in cement.  
Pulled tubing to 3000' - spotted 15 sxs gel.  
Pulled tubing to 1800' - spotted 125 sxs cement with 200# hulls in cement.  
Pulled tubing to 300' - spotted 20 sxs cement to circulate at surface.  
Pulled tubing and filled casing with 10 sxs cement.  
8 5/8" S.P. Squeezed 15 sxs cement.  
Max. P.S.I. 500#. S.I.P. 500#.

INVOICED  
DATE 4-5-01  
INV. NO. 2001061584

RECEIVED  
STATE CORPORATION COMMISSION

APR - 4 2001  
04-04-01  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04


Signed Dennis J. Hamel  
(TECHNICIAN)

100

APR 02 2001

40

SOHIO PETROLEUM COMPANY      REPLACEMENT CARD      12-10-20W  
 50 PENN PLACE, #1100      #9 DESBIEN      685'FNL &  
 OKLA. CITY, OK 73118      1665'FEL, NE/4  
 CONTR WHITE & ELLIS DRILLING      CTY ROOKS  
 GEOL STEVE BRACHMAN      FIELD MARCOTTE



ELV 2226 KB SPD 12/4/84      CARD ISSUED 2/28/85      IP P 29 B0 & 40 BWPD  
2221 GL DRLG COMP 12/10/84      LKC 3602-3682 OA  
 API 15-163-22,502

LOG	Tops	Depth/Datum
ANH	.....	1647+ 579
DOVER LM	.....	3010- 784
TARK LM	.....	3042- 816
ELM LM	.....	3080- 854
HOW LM	.....	3162- 936
TOP LM	.....	3226-1000
HEEB SH	.....	3431-1205
TOR 'M	.....	3451-1225
LKC	.....	3469-1243
BKC	.....	3685-1459
B/PENN CONG	.....	3726-1500
ARB	.....	3779-1553
PBTD	.....	3760-1534
RTD	.....	4133-1907

8 5/8 " 282 / 170SX, 5 1/2 " 3865 / 625SX  
 MICT - CO, PF (LKC) 3676-82, 3668-69 & 3659-63, W / 4 SPF,  
 AC 4600G, SWB DWN, GSO, PF (LKC) 3638-41, 3622-27 & 3602-  
 06, W / 4 SPF, AC 1100G, SWB DWN, GSO, T&R, POP, P 29 B0  
 & 40 BWPD, (GR 32.4%), 1/28/85

INFO RELEASED: 5/2/85 - WAS OIL WELL - TIGHT HOLE  
 NOTE: CORRECTION: 12/13/84 - ORIGINALLY FIRST REPORTED IN  
 760'FNL&1740'FEL, NE/4