

12-30

6 041126

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 163-02,071-00-00
SE SE SE 12 10 20
SEC. T S, R W&E

TECHNICIAN'S PLUGGING REPORT

Operator License # 6854
Operator: B. P. Exploration Inc.
Name & Address: Box 37
Gorham, Ks. 67640

330 feet from S section line
330 feet from E section line
Lease Name Sutor Well # 1
County Rooks 12272
Well Total Depth 3776 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 1659' w/625s

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton Cementing License Number
Address Hays, Ks.

Company to plug at: Hour: 9:00 AM Day: 29 Month: Dec Year: 19 89

Plugging proposal received from Joel Stull
(company name) B. P. Exp (phone)

were: 5 1/2" set at 3774' w/100 sks; Perf at 3522' - 3679'.
Ordered 350 sks 65/35 poz 10% gel w/5 sks hulls.

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None
Operations Completed: Hour: 12:30PM Day: 30 Month: Dec Year: 19 89

ACTUAL PLUGGING REPORT Set EZSV at 3450': Sq. 85 sks cement to
500# psi and spotted 100' of cement on top of retainer. circ gel to 1700': Perf
casing at 1664: Circ fluid to surf; (120)sk.: pulled tubing and sq 145 sks cement at
surface, cement did not circ: shut down/ (12-30-89, TOC.524': perf at 500' and 300'
ran tubing to 500' and circ cement to surface w/100 sks. pulled tubing and sq add 15 sk
cement to 300#. Max S.I. 300#.

RECEIVED
STATE CORPORATION COMMISSION
1-17-90
JAN 17 1990

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED
JAN 24 1990

DATE
INV. NO. 27094
12-30

J.S.

Signed Dennis L. Hamel
(TECHNICIAN)
Dennis L. Hamel

CONSERVATION DIVISION
Wichita, Kansas