

4-042059

API Number: 15-163-03528-0000
01-51

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

SW SE NE /4 SEC. 12 10
05 12 S, 20 W
2970 feet from S section line
990 feet from E Section line

Operator license# 5030
Operator: Vess Oil Corporation
Address: 8100 E. 22nd St. N. Bldg 300
Wichita, Kansas 67226

6/15

Lease: Desbien Well # 3
County: Rooks 122.79
Well total depth 3778 feet
Conductor Pipe: inch @ feet
Surface Pipe: 8 5/8 Inch 303 Feet
W/200 sx.cmt

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License#

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00 A.M. Day: 15 Month: June Year 2000

Plugging proposal received from: Joe Stull

Company: Vess Oil Corporation Phone:

Were: Ordered 250 sxs 60/40 pozmix - 10% gel - 1/4# F.C. plus 300# hulls.
5 1/2" casing set at 3774' w/150 sxs cement. Perf at 3628' - 3778'.
5 1/2" casing squeeze: 1952 Dakota squeezed cement N/A;
1962 at 1575' w/85 sxs; 1963 at 1377' w/85 sxs; 1963 at 1302' w/55 sxs;
1973 repair casing cement and footage N/A; 1984 at 0' - 900' w/300 sxs,
125 sxs, 125 sxs, 145 sxs (4 squeezes). Tubing fish at 1532'.

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 10:45 A.M., Day 15, Month: June, Year: 2000

Actual plugging report: RIH with tubing to 1500'. Spotted 150 sxs cement to circulate at surface. POOH with tubing and squeezed casing with additional 35 sxs cement.
Max. P.S.I. 600#. S.I.P 400#. 8 5/8" - Rigged up cementers to 5 1/2" annulus, pressured up to 1500#. Job complete.

Remarks:
Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING X CASING . Elevation: G.L.

I did[X] / did not[] observe the plugging.

INVOICED
DATE 7/25/00
INV. NO. 1060127

Dennis J. Hamel
(agent)
RECEIVED
STATE CORPORATION COMMISSION
7-20-00
JUL 20 2000
Form CP-2/3
CONSERVATION DIVISION
Wichita, Kansas