

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-02083-00-02
Spot: SENESW Sec/Twnshp/Rge: 12-10S-20W
1650 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: SUTOR B Well Number: 3
County: ROOKS Total Vertical Depth: 3820 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

Conductor Pipe: Size feet: #12 4.15
Surface Casing: Size 8.625 feet: 1647 w/800 sxs cmt
Production: Size 5.5 feet: 3758 w/150 sxs cmt
Liner: Size 4.5 feet: 3820 w/50 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/12/2001 3:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2537

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 10% gel - 500# hulls.
Sand bottom to 3550' plus 5 sxs cement.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 02/12/2001 4:30 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Shot casing at 2500' - pulled casing to 2150' - spotted 150 sxs cement with 300# hulls mixed in cement.
Pulled casing to 1650' - spotted 40 sxs plus 100# hulls.
Pulled casing to 950' - spotted 40 sxs cement plus 100# hulls.
Pulled casing to 200' - spotted 45 sxs cement to circulated at surface.
Pulled casing with cement in cellar.
Job complete.

INVOICED
DATE 03-08-2001
WV. NO. 2001061471
RECEIVED
KANSAS CORPORATION COMMISSION
2-28-01
FEB 28 2001
CONSERVATION DIVISION

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04


Signed

Dennis L. Hamel

(TECHNICIAN)

"B"

STATE	KANS	COUNTY	ROOKS	OWWO	12-10S-20W
FIELD	MARCOTTE (MULTIPAY)				SE NE SW
OPER	TEX-CON O&G				1650FSL 2970FEL SEC
WELL	3 SUTOR "B"			WELL CLASS	DO
API	15-163-02083-0002			STATUS	OIL-WO
SPUD	08/22/1990			COMP	08/31/1990
DTD	3820	LTD		PSTD	3730
		FTD	ARBUCKLE		



LOC

Petroleum Information Corporation

IPP 14 BOPD 106 BW
 PROD ZONE: LSG-KANSAS CITY 3594-3674 GROSS
 FIRST REPORT & COMPLETION

EL: 2218 GR

TBGS: 2 3/8 @ 3709 W/PKR @ 3694

OWWO: OLD INFO: FORMERLY B P EXPL 3 SUTOR "B". RE-SPUD 10/28/88. 4 1/2 LNR @ 3401-3820. LOG TOPS: ARBUCKLE 3760. OTD 3820. COMP 11/30/88. IPP 23 BO, 1852 BWP. PROD ZONE: ARBUCKLE 3772-3790 GROSS.

NEW: BRPG @ 3740 W/10 FT

PERFS: LANSING-KANSAS CITY PERF W/ 2/FT 3594-3674 GROSS
 3594-3598 3602-3606 3614-3620 3630-3636
 3638-3642 3650-3654 3656-3659 3668-3674
 ACID 3000 GALS 15% HCL

OPER ADDRESS: 9402 SOUTHWEST FREEWAY, HOUSTON, TX 77074

KS 8-020591