

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-19011-00-00<sup>0001</sup>  
Spot: SENWSE Sec/Twnshp/Rge: 12-10S-20W  
1650 feet from S Section Line, 1650 feet from E Section Line  
Lease/Unit Name: EARL SUTOR Well Number: 5  
County: ROOKS Total Vertical Depth: 3764 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 8100 E. 22ND N. BLDG. 300  
WICHITA, KS 67226

Conductor Pipe: Size feet: 4 1/2 2.33  
Surface Casing: Size 8.625 feet: 1668 675 SX CMT  
Production: Size 5.5 feet: 3765 100 SX CMT  
Liner: Size feet:

Well Type: EOR UIC Docket No: E26024.2 Date/Time to Plug: 01/25/2001 10:00 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTY ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2537

Proposed Plugging Method: Ordered 270 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: HERB DEINES

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 01/25/2001 12:00 PM

KCC Agent: DENNIS HAMEL

**Actual Plugging Report:**

R.U. Casing pullers - took stretch - shot casing off at 2710'.  
Pulled to 2150' - spotted 150 sxs cement with 300# hulls.  
Pulled casing to 1650' - spotted 40 sxs cement with 100# hulls.  
Pulled casing to 950' - spotted 40 sxs cement with 100# hulls.  
Pulled casing to 209' - spotted 45 sxs cement to circulate at surface.  
Pulled balance of casing with cement in cellar.  
Job complete.

INVOICED  
DATE 03-08-2001  
INV. NO. 2001061451

RECEIVED  
STATE CORPORATION COMMISSION  
2-14-01  
FEB 14 2001

Remarks: ALLIED CEMENTING COMPNAVY.

Plugged through: CSG

CONSERVATION DIVISION  
WICHITA, KANSAS

District: 04

*100*

Signed

Dennis L. Hamel  
(TECHNICIAN)

Enal

GULF OIL CORPORATION #5 SUTOR 12-10-20W 22  
SE NW SE


Contr. \_\_\_\_\_ ROOKS County

E 2232 Comm. \_\_\_\_\_ Comp. 11-10-50 IP 3000 BOPD  
DRAW DOWN

Tops	Depth	Datum
ANH	1658	+ 574
HEEB	3431	- 1199
LANS	3471	- 1239
CONG	3712	- 1480
SIMP	3742	- 1510
ARB	3764	- 1532
T.D.	3771	- 1539

Casing  
 8" 1668 DP 3768  
 5" 3765<sup>1</sup>/<sub>2</sub> SWB 58 BOPH  
 ACID 500  
 DD 3771  
 SWB 229 B0/4 HRS

BERLAND POOL



8<sup>5</sup>/<sub>8</sub> 1668  
 5<sup>1</sup>/<sub>2</sub> 3765

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS